



February 9, 2004

State of Utah
Division of Oil, Gas & Mining
Attn: Diana Whitney
1594 West North Temple - Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Applications for Permit to Drill: Federal 1-4-9-18, 7-4-9-18, 9-4-9-18, and
15-4-9-18.

Dear Diana:

Enclosed find APD's on the above referenced wells. If you have any questions, feel free
to give either Brad or myself a call.

Sincerely,

Mandie Crozier
Regulatory Specialist

mc
enclosures

RECEIVED

FEB 10 2004

DIV. OF OIL, GAS & MINING

001

Form 3160-3
(September 2001)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER



FORM APPROVED
OMB No. 1004-0136
Expires January 31, 2004

| | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------|
| 1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER | | 5. Lease Serial No. U-17424 |
| 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone | | 6. If Indian, Allottee or Tribe Name N/A |
| 2. Name of Operator Inland Production Company | | 7. If Unit or CA Agreement, Name and No. N/A |
| 3a. Address Route #3 Box 3630, Myton UT 84052 | | 8. Lease Name and Well No. Federal 7-4-9-18 |
| 3b. Phone No. (include area code) (435) 646-3721 | | 9. API Well No. 43-047-35474 |
| 4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface SW/NE 1984' FNL 1979' FEL 4434991Y 40.06180 At proposed prod. zone 594195X -109.89554 | | 10. Field and Pool, or Exploratory Eight Mile Flat |
| 11. Sec., T., R., M., or Blk. and Survey or Area SW/NE Sec. 4, T9S R18E | | 12. County or Parish Uintah |
| 13. State UT | | |
| 14. Distance in miles and direction from nearest town or post office* Approximatley 20.8 miles southeast of Myton, Utah | 15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) Approx. 664' f/lse, NA f/unit | 16. No. of Acres in lease 639.84 |
| 17. Spacing Unit dedicated to this well 40 Acres | 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 2400' | 19. Proposed Depth 6500' |
| 20. BLM/BIA Bond No. on file #4488944 | 21. Elevations (Show whether DF, KDB, RT, GL, etc.) 4937' GL | 22. Approximate date work will start* 2nd Quarter 2004 |
| 23. Estimated duration Approximately seven (7) days from spud to rig release. | | |

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

| | | |
|---------------------------------------------------------------------------------------------------------------|-----------------------------------------|------------------|
| 25. Signature  | Name (Printed/Typed) Mandie Crozier | Date 2/9/04 |
| Title Regulatory Specialist | | |
| Approved by (Signature)  | Name (Printed/Typed) BRADLEY G. HILL | Date 02-12-04 |
| Title ENVIRONMENTAL SCIENTIST III | | |

Federal Approval of this
Action is NecessaryApplication approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

RECEIVED
FEB 10 2004
DIV. OF OIL, GAS & MINING

INLAND PRODUCTION COMPANY

 = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (PARIETTE DRAW SW)



THIS IS TO CERTIFY THAT THE ABOVE MAP WAS
PREPARED FROM FIELD NOTES OF AERIAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST OF
MY KNOWLEDGE AND BELIEF.

STACY W
STEWART

REGISTERED LAND SURVEYOR
REGISTRATION No. 189377
STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

SCALE: 1" = 1000'

SURVEYED BY: K.G.S.

DATE: 10-9-03

DRAWN BY: J.R.S.

NOTES:

FILE #

**INLAND PRODUCTION COMPANY
FEDERAL #7-4-9-18
SW/NE SECTION 4, T9S, R18E
UINTAH COUNTY, UTAH**

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

| | |
|-------------|------------|
| Uinta | 0' - 1640' |
| Green River | 1640' |
| Wasatch | 6050' |

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation 1640' - 6500' - Oil

4. PROPOSED CASING PROGRAM

Please refer to the Monument Butte Field Standard Operation Procedure (SOP).

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

Please refer to the Monument Butte Field SOP. See Exhibit "C".

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

Please refer to the Monument Butte Field SOP.

7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Please refer to the Monument Butte Field SOP.

8. TESTING, LOGGING AND CORING PROGRAMS:

Please refer to the Monument Butte Field SOP.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

The anticipated maximum bottom hole pressure is 2000 psi. It is not anticipated that abnormal temperatures will be encountered.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

Please refer to the Monument Butte Field SOP.

**INLAND PRODUCTION COMPANY
FEDERAL #7-4-9-18
SW/NE SECTION 4, T9S, R18E
UINTAH COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Inland Production Company well location site Federal #7-4-9-18 located in the SW 1/4 NE 1/4 Section 4, T9S, R18E, Uintah County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.6 miles \pm to the junction of this highway and UT State Hwy 53; proceed southeasterly along Hwy 53 - 11.7 miles \pm to it's junction with an existing road to the southeast; proceed southeasterly - 3.6 miles \pm to it's junction with an existing road to the east; proceed northeasterly - 1.7 miles \pm to it's junction with an existing road to the northeast; proceed northeasterly - 2.2 miles \pm to it's junction with the beginning of the proposed access road; proceed northwesterly along the proposed access road 160' \pm to the proposed well location.

2. PLANNED ACCESS ROAD

See Topographic Map "B" for the location of the proposed access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

Please refer to the Monument Butte Field Standard Operating Procedure (SOP).

5. LOCATION AND TYPE OF WATER SUPPLY

Please refer to the Monument Butte Field SOP. See Exhibit "A".

6. SOURCE OF CONSTRUCTION MATERIALS

Please refer to the Monument Butte Field SOP.

7. METHODS FOR HANDLING WASTE DISPOSAL

Please refer to the Monument Butte Field SOP.

8. ANCILLARY FACILITIES

Please refer to the Monument Butte Field SOP.

9. **WELL SITE LAYOUT**

See attached Location Layout Diagram.

10. **PLANS FOR RESTORATION OF SURFACE**

Please refer to the Monument Butte Field SOP.

11. **SURFACE OWNERSHIP** - Bureau Of Land Management

12. **OTHER ADDITIONAL INFORMATION**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. MOAC Report #03-154, 2/3/04. Paleontological Resource Survey prepared by, Wade E. Miller, 11/15/03. See attached report cover pages, Exhibit "D".

Inland Production Company requests a 60' ROW for the Federal #7-4-9-18 to allow for construction of a 6" gas gathering line, and a 3" poly fuel gas line. Both lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** For a ROW plan of development, please refer to the Monument Butte Field SOP.

Inland Production Company also requests a 60' ROW be granted for the Federal #7-4-9-18 to allow for construction of a 3" steel water injection line and a 3" poly water return line. **Refer to Topographic Map "C."** For a ROW plan of development, please refer to the Monument Butte Field SOP.

Water Disposal

Please refer to the Monument Butte Field SOP.

Reserve Pit Liner

Please refer to the Monument Butte Field SOP.

Location and Reserve Pit Reclamation

Please refer to the Monument Butte Field SOP.

The following seed mixture will be used on the topsoil stockpile, the recontoured surface of the reserve pit, and for final reclamation: (All poundages are in pure live seed)

| | | |
|-------------------|-------------------------------|------------|
| Shadscale | <i>Atriplex confertifolia</i> | 4 lbs/acre |
| Gardners Saltbush | <i>Atriplex corrugata</i> | 4 lbs/acre |
| Galleta Grass | <i>Hilaria jamesii</i> | 4 lbs/acre |

Details of the On-Site Inspection

The proposed Federal #7-4-9-18 was on-sited on 8/20/03. The following were present; Brad Mecham (Inland Production), Byron Tolman (Bureau of Land Management), and a SWCA representative. Weather conditions were clear.

13. **LESSEE'S OR OPERATORS REPRESENTATIVE AND CERTIFICATION**

Representative

Name: Brad Mecham

Address: Route #3 Box 3630

Myton, UT 84052

Telephone: (435) 646-3721

Certification

Please be advised that INLAND PRODUCTION COMPANY is considered to be the operator of well #7-4-9-18 SW/NE Section 4, Township 9S, Range 18E: Lease U-17424 Uintah County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4488944.

I hereby certify that the proposed drillsite and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Inland Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

2/19/04

Date


Mandie Crozier
Mandie Crozier
Regulatory Specialist

INLAND PRODUCTION COMPANY

FEDERAL 7-4-9-18

Section 4, T9S, R18E, S.L.B.&M.

PROPOSED ACCESS
ROAD (Max. 6% Grade)



C/0.1

②

STA. 2+90

C/2.3

③

④

C/2.6

2' Berm Around
Fill Portion of Location

STA. 2+22

PIT TOPSOIL
STOCKPILE

C/3.6

Top of
Cut Slope

F/0.3

①

120'

STA. 1+60

C/0.8

⑤

⑥

C/0.8

Toe of
Fill Slope

WELL HEAD:
UNGRADED = 4937.2'
FIN. GRADE = 4936.4'

Existing
Drainage

EXCESS
MATERIAL

CONSTRUCT
DIVERSION DITCH

STA. 0+00

160'

⑧

F/0.3

C/1.0

⑦

⑥

C/1.2

REFERENCE POINTS

210' NORTHWEST = 4937.7'
260' NORTHWEST = 4937.7'
170' NORTHEAST = 4935.5'
220' NORTHEAST = 4935.1'

SURVEYED BY: K.G.S.

SCALE: 1" = 50'

DRAWN BY: J.R.S.

DATE: 10-9-03

Tri State
Land Surveying, Inc.





(435) 781-2501

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

INLAND PRODUCTION COMPANY

CROSS SECTIONS

FEDERAL 7-4-9-18



ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)

| ITEM | CUT | FILL | 6" TOPSOIL | EXCESS |
|--------|-------|------|------------------------------------|--------|
| PAD | 810 | 810 | Topsoil is not included in Pad Cut | 0 |
| PIT | 640 | 0 | | 640 |
| TOTALS | 1,450 | 810 | 890 | 640 |

NOTE:
UNLESS OTHERWISE NOTED
ALL CUT/FILL SLOPES ARE
AT 1.5:1

SURVEYED BY: K.G.S.

SCALE: 1" = 50'

DRAWN BY: J.R.S.


DATE: 10-9-03

Tri State
Land Surveying, Inc.
(435) 781-2501
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

INLAND PRODUCTION COMPANY

TYPICAL RIG LAYOUT

FEDERAL 7-4-9-18



SURVEYED BY: K.G.S.

SCALE: 1" = 50'

DRAWN BY: J.R.S.


DATE: 10-9-03

Tri State
Land Surveying, Inc.

(435) 781-2501

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

"A"



Federal 7-4-9-18
SEC. 4, T9S, R18E, S.L.B.&M.



Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078


SCALE: 1" = 2,000'
 DRAWN BY: R.A.B.
 DATE: 10-20-2003

Legend

- Existing Road
- Proposed Access

TOPOGRAPHIC MAP

"B"



Federal 7-4-9-18
SEC. 4, T9S, R18E, S.L.B.&M.



Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078


SCALE: 1" = 2,000'
DRAWN BY: R.A.B.
DATE: 10-28-2003

Legend

- Roads
- Existing Gas Line
- Proposed Gas Line
- Existing Water Line
- Proposed Water Line

TOPOGRAPHIC MAP

"C"



January 15, 2003

Exhibit "B"

2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

CULTURAL RESOURCE INVENTORY OF
INLAND PRODUCTIONS PARCEL IN
T 8 S, R18 E, SEC. 33 AND
T 9 S, R 18 E, SEC. 3 & 4,
UINTAH COUNTIES, UTAH

BY:

Katie Simon
and
Keith R. Montgomery

Prepared For:

Bureau of Land Management
Vernal Field Office

Prepared Under Contract With:

Inland Production
Route 3, Box 3630
Myton, UT 84052

Prepared By:

Montgomery Archaeological Consultants
P.O. Box 147
Moab, Utah 84532

MOAC Report No. 03-154

February 3, 2004

United States Department of Interior (FLPMA)
Permit No. 03-UT-60122

State of Utah Antiquities Project (Survey)
Permit No. U-03-MQ-0799b

INLAND RESOURCES, INC.

**PALEONTOLOGICAL FIELD SURVEY OF PROPOSED
PRODUCTION DEVELOPMENT AREAS,
UINTAH COUNTY, UTAH**

(Sections 3, 4, & 10, T 9 S, R 18 E; Section 7, T 9 S, R 19 E)

REPORT OF SURVEY

Prepared for:

Inland Resources, Inc.

Prepared by:

Wade E. Miller
Consulting Paleontologist
November 15, 2003

003

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 02/10/2004

API NO. ASSIGNED: 43-047-35474

WELL NAME: FEDERAL 7-4-9-18OPERATOR: INLAND PRODUCTION (N5160)CONTACT: MANDIE CROZIERPHONE NUMBER: 435-646-3721

PROPOSED LOCATION:

SWNE 04 090S 180E

SURFACE: 1984 FNL 1979 FEL

BOTTOM: 1984 FNL 1979 FEL

UINTAH

8 MILE FLAT NORTH (590)

LEASE TYPE: 1 - Federal

LEASE NUMBER: U-17424

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: GRRV

COALBED METHANE WELL? NO

INSPECT LOCATN BY: / /

| Tech Review | Initials | Date |
|-------------|----------|------|
| Engineering | | |
| Geology | | |
| Surface | | |

LATITUDE: 40.06180

LONGITUDE: 109.89554

RECEIVED AND/OR REVIEWED:

- ☒ Plat
- ☒ Bond: Fed[1] Ind[] Sta[] Fee[]
 (No. 4488944)
- ☒ Potash (Y/N)
- ☒ Oil Shale 190-5 (B) or 190-3 or 190-13
- ☒ Water Permit
 (No. MUNICIPAL)
- ☒ RDCC Review (Y/N)
 (Date: _____)
- ☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:


- ☐ R649-2-3.
- Unit _____
- ☒ R649-3-2. General
 Siting: 460 From Qtr/Qtr & 920' Between Wells
- ☐ R649-3-3. Exception
- ☐ Drilling Unit
 Board Cause No: _____
 Eff Date: _____
 Siting: _____
- ☐ R649-3-11. Directional Drill

COMMENTS:

See Separate file

STIPULATIONS:

1- Federal approval
2- Spacing Map




OPERATOR: INLAND PROD CO (N5160)

SEC. 4 T.9S, R.18E

FIELD: EIGHT MILE NORTH FLAT (590)

COUNTY: UINTAH

SPACING: R649-3-2 / GENERAL SITING



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 11-FEBRUARY-2004



State of Utah

Department of
Natural Resources

Division of
Oil, Gas & Mining

ROBERT L. MORGAN
Executive Director

LOWELL P. BRAXTON
Division Director

MICHAEL O. LEAVITT
Governor

OLENE S. WALKER
Lieutenant Governor

February 12, 2004

Inland Production Company
Route #3, Box 3630
Myton, UT 84052

Re: Federal 7-4-9-18 Well, 1984' FNL, 1979' FEL, SW NE, Sec. 4, T. 9 South,
R. 18 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-35474.

Sincerely,

A handwritten signature in black ink, appearing to read "John R. Baza".

John R. Baza
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Inland Production Company
Well Name & Number Federal 7-4-9-18
API Number: 43-047-35474
Lease: U-17424

Location: SW NE Sec. 4 T. 9 South R. 18 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

005

Form 3160-3
(September 2001)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0136
Expires January 31, 2004

| |
|----------------------------------------------------------------------------|
| 5. Lease Serial No. U-17424 |
| 6. If Indian, Allottee or Tribe Name N/A |
| 7. If Unit or CA Agreement, Name and No. N/A |
| 8. Lease Name and Well No. Federal 7-4-9-18 |
| 9. API Well No. 43,047,35474 |
| 10. Field and Pool, or Exploratory Eight Mile Flat |
| 11. Sec., T., R., M., or Blk. and Survey or Area SW/NE Sec. 4, T9S R18E |
| 12. County or Parish Utah |
| 13. State UT |

1a. Type of Work: ☒ DRILL ☐ REENTER1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator

Newfield Production Company

3a. Address

Route #3 Box 3630, Myton UT 84052

3b. Phone No. (include area code)

(435) 646-3721

4. Location of Well (Report location clearly and in accordance with any State requirements. *)

At surface SW/NE 1984' FNL 1979' FEL

At proposed prod. zone

14. Distance in miles and direction from nearest town or post office*

Approximately 20.8 miles southeast of Myton, Utah

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) Approx. 664' f/lse, NA f/unit

16. No. of Acres in lease

639.84

17. Spacing Unit dedicated to this well

40 Acres

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 2400'

19. Proposed Depth

6500'

20. BLM/BIA Bond No. on file

#4488944

21. Elevations (Show whether DF, KDB, RT, GL, etc.)

4937' GL

22. Approximate date work will start*

2nd Quarter 2004

23. Estimated duration

Approximately seven (7) days from spud to rig release.

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized officer.

RECEIVED

DEC 06 2004

DIV. OF OIL, GAS & MINING

25. Signature

Mandie Crozier

Name (Printed/Typed)

Mandie Crozier

Date

2/9/04

Title

Regulatory Specialist

Approved by (Signature)

Thomas B. Crozier

Name (Printed/Typed)

Office

Date

12/02/2004

Title

Mineral Resources

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

NOTICE OF APPROVAL

UDOGM

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Newfield Production Company.

Well Name & Number: Federal 7-4-9-18

API Number: 43-047-35474

Lease Number: U-17424

Location: SWNE Sec. 4 T. 9S R. 18E

Agreement: N/A

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

Please submit to this office, in LAS format, an electronic copy of all logs run on this well. This submission will replace the requirement for submittal of paper logs to the BLM.

In the event after-hours approvals are necessary, you must contact one of the following individuals:

Ed Forsman (435) 828-7874
Petroleum Engineer

Kirk Fleetwood (435) 828-7875
Petroleum Engineer

BLM FAX Machine (435) 781-4410

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

No construction or drilling shall be allowed during the burrowing owl nesting season (April 1 to Aug. 15), without first consulting the BLM biologist. If no nesting owls are found, drilling will be allowed.

DIVISION OF OIL, GAS AND MINING**SPUDDING INFORMATION**Name of Company: INLAND PRODUCTION COMPANYWell Name: FEDERAL 7-4-9-18Api No: 43-047-35474 Lease Type: FEDERALSection 04 Township 09S Range 18E County UINTAHDrilling Contractor NDSI RIG # NS#1**SPUDDED:**Date 01/10/2005Time 1:00 PMHow DRY**Drilling will commence:** _____Reported by FLOYD MITCHELLTelephone # 1-435-823-3610Date 01/10/2005 Signed CHD

007

PAGE 02

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

Inland
OPERATOR: NEWFIELD PRODUCTION COMPANY
ADDRESS: RT. 3 BOX 3630
MYTON, UT 84082

RECEIVED

JAN 12 2005

DIV. OF OIL, GAS & MINING

N5160

OPERATOR ACCT. NO. N2695

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|------------------------------|--------------------|----------------|--------------|-----------------------------|---------------|----|----|-----|--------|------------------|----------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| A | 99999 | 14497 | 43-047-35518 | Federal 12-12-9-17 | NW/SW | 12 | 9S | 17E | Utah | January 4, 2005 | 1/13/05 |
| WELL 1 COMMENTS: <i>GRRV</i> | | | | | | | | | | | |
| A | 99999 | 14498 | 43-047-35749 | Federal 6-12-9-17 | SE/NW | 12 | 9S | 17E | Utah | January 6, 2005 | 1/13/05 |
| WELL 2 COMMENTS: <i>GRRV</i> | | | | | | | | | | | |
| B | 99999 | 12308 | 43-013-32376 | Sandwash Federal 14-19-8-17 | SE/SW | 19 | 8S | 17E | Utah | January 10, 2005 | 1/13/05 |
| WELL 3 COMMENTS: <i>GRRV</i> | | | | | | | | | | | |
| A | 99999 | 14499 | 43-047-35474 | Federal 7-4-9-18 | SW/NE | 4 | 9S | 18E | Utah | January 10, 2005 | 1/13/05 |
| WELL 4 COMMENTS: <i>GRRV</i> | | | | | | | | | | | |
| A | 99999 | 14500 | 43-047-35517 | Federal 14-12-9-17 | SE/SW | 12 | 9S | 17E | Utah | January 11, 2005 | 1/13/05 |
| WELL 5 COMMENTS: <i>GRRV</i> | | | | | | | | | | | |

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or east well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/95)

Kebbie S. Jones
Signature
Production Clerk
Title

Kebbie S. Jones

January 12, 2005

Date

INLAND

4356463831

01/12/2005 14:55

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED
JAN 14 2005

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

COPY

008

SUNDRY NOTICES AND REPORTS ON WELLS OIL, GAS & MINING
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address

Route 3 Box 3630
Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1984 FNL 1979 FEL
SW/NE Section 4 T9S R18E

5. Lease Serial No.

UTU17424

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

FEDERAL 7-4-9-18

9. API Well No.

4304735474

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State

Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|-------------------------------------------------------|----------------------------------------------|-------------------------------------------|---------------------------------------------------|-------------------------------------------------|
| <input type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production(Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Subsequent Report | <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other _____ |
| | <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug & Abandon | <input type="checkbox"/> Temporarily Abandon | Spud Notice |
| | <input type="checkbox"/> Convert to Injector | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 01-10-05 MIRU NDSI NS # 1. Spud well @ 1:00 PM. Drill 305' of 12 1/4" hole with air mist. TIH W/ 7 Jt's 8 5/8" J-55 24 # csgn. Set @ 306.39' KB On 01/12/05 cement with 160 sks of class "G" w/ 3% CaCL2 + 1/4# sk Cello- Flake Mixed @ 15.8 ppg > 1.17 cf/ sk yeild. Returned 6 bbls cement to pit. WOC.

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)
Floyd Mitchell

Title

Drilling Supervisor

Signature

Date

1/13/2005

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8 CASING SET AT 306.39

LAST CASING 8 5/8" SET AT 306.39
 DATUM 12' KB
 DATUM TO CUT OFF CASING _____
 DATUM TO BRADENHEAD FLANGE _____
 TD DRILLER 305' LOGGER N/A
 HOLE SIZE 12 1/4

OPERATOR Newfield Production
 WELL Federal 7-4-9-18
 FIELD/PROSPECT Monument Butte
 CONTRACTOR & RIG # NDSI NS # 1

| LOG OF CASING STRING: | | | | | | | |
|-------------------------------------------------------|--------|-------------------------------------------------------------------------------|---------|----------------------------------------|--------|-------|--------|
| PIECES | OD | ITEM - MAKE - DESCRIPTION | WT / FT | GRD | THREAD | CONDT | LENGTH |
| | | 40.30' SH jt | | | | | |
| | | WHI - 92 csg head | | | 8rd | A | 0.95 |
| 7 | 8 5/8" | Maverick ST&C csg | 24# | J-55 | 8rd | A | 294.54 |
| | | GUIDE shoe | | | 8rd | A | 0.9 |
| CASING INVENTORY BAL. | | FEET | JTS | TOTAL LENGTH OF STRING | | | |
| | | 296.39 | 7 | LESS CUT OFF PIECE | | | |
| LESS NON CSG. ITEMS | | 1.85 | | PLUS DATUM TO T/CUT OFF CSG | | | |
| PLUS FULL JTS. LEFT OUT | | 0 | | CASING SET DEPTH | | | |
| TOTAL | | 294.54 | 7 | 296.39 | | | |
| TOTAL CSG. DEL. (W/O THRS) | | 294.54 | 7 | 2 | | | |
| TIMING | | 1ST STAGE | | 12 | | | |
| BEGIN RUN CSG. | Spud . | 1/10/2005 | 1:00 PM | COMPARE | | | |
| CSG. IN HOLE | | 1/12/2005 | 4:00 PM | GOOD CIRC THRU JOB <u>Yes</u> | | | |
| BEGIN CIRC | | 1/12/2005 | 5:35 PM | Bbls CMT CIRC TO SURFACE <u>6</u> | | | |
| BEGIN PUMP CMT | | 1/12/2005 | 5:48 PM | RECIPROCATED PIPE IN/A _____ | | | |
| BEGIN DSPL. CMT | | 1/12/2005 | 17:59 | DID BACK PRES. VALVE HOLD ? <u>N/A</u> | | | |
| PLUG DOWN | | 1/12/2005 | 6:07 PM | BUMPED PLUG TO <u>591</u> PSI | | | |
| CEMENT USED | | CEMENT COMPANY- <u>B. J.</u> | | | | | |
| STAGE | # SX | CEMENT TYPE & ADDITIVES | | | | | |
| 1 | 160 | Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield | | | | | |
| CENTRALIZER & SCRATCHER PLACEMENT | | SHOW MAKE & SPACING | | | | | |
| Centralizers - Middle first, top second & third for 3 | | | | | | | |

COMPANY REPRESENTATIVE Floyd Mitchell DATE 1/13/2005

4/22/05
FORM 3160-5
(September 2001)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

009

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator
Newfield Production Company

3a. Address Route 3 Box 3630
Myton, UT 84052

3b. Phone No. (include area code)
435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
1984 FNL 1979 FEL
SW/NE Section 4 T9S R18E

5. Lease Serial No.

UTU17424

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

FEDERAL 7-4-9-18

9. API Well No.

4304735474

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State

Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|-------------------------------------------------------|----------------------------------------------|-------------------------------------------|----------------------------------------------------|-------------------------------------------------|
| <input type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Subsequent Report | <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recombine | <input checked="" type="checkbox"/> Other _____ |
| | <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug & Abandon | <input type="checkbox"/> Temporarily Abandon | Weekly Status Report |
| | <input type="checkbox"/> Convert to Injector | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 1/14/2005 MIRU Patterson Rig # 155. Set all equipment. Pressure test Kelly, TIW, Choke manifold, & Bop's to 2,000 psi. Test 8.625 csgn to 1,500 psi. Vernal BLM field, & Roosevelt DOGM office was notified of test. PU BHA and tag cement @ 260'. Drill out cement & shoe. Drill a 7.875 hole with fresh water to a depth of 6,010'. Lay down drill string & BHA. Open hole log w/ Dig/SP/GR log's TD to surface. PU & TIH with Guide shoe, shoe jt, float collar, 139 jt's of 5.5 J-55, 15.5# csgn. Set @ 5996.71' / KB. Cement with 350sks cement mixed @ 11.0 ppg & 3.43 yd. The 500 sks cement mixed @ 14.4 ppg & 1.24 yd. With all spacers returned to pit. Nipple down Bop's. Drop slips @ 85,000 #'s tension. Release rig 3:00 am on 01-19-05.

RECEIVED

JAN 21 2005

OIL & GAS MINING

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)
Floyd Mitchell

Title

Drilling Supervisor

Signature

Floyd Mitchell

Date

1/19/2005

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

010

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1984 FNL 1979 FEL

SW/NE Section 4 T9S R18E

5. Lease Serial No.

UTU17424

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

FEDERAL 7-4-9-18

9. API Well No.

4304735474

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State

Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|-------------------------------------------------------|----------------------------------------------|-------------------------------------------|----------------------------------------------------|-------------------------------------------------|
| <input type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Subsequent Report | <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other _____ |
| | <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug & Abandon | <input type="checkbox"/> Temporarily Abandon | Weekly Status Report |
| | <input type="checkbox"/> Convert to Injector | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Status report for time period 02/07/2005-02/16/2005

Subject well had completion procedures initiated in the Green River formation on 02/07/05 without the use of a service rig over the well. A cement bond log was run and a total of three Green River intervals were perforated and hydraulically fracture treated w/ 20/40 mesh sand. Perf intervals were #1 (5722-5747'), (5680-5697') (All 4JSPF); #2 (5137'-5146') (4 JSPF); #3 (4759-4779') (4 JSPF). Composite flow-through frac plugs were used between stages. Fracs were flowed back through chokes. A service rig was moved on well on 2/14/05. Bridge plugs were drilled out. Well was cleaned out to PBTD @ 5955'. Zones were swab tested for sand cleanup. A BHA & production tbg string were run in and anchored in well. End of tubing string @ 5833'. A new 1 1/2" bore rod pump was run in well on sucker rods. Well was placed on production via rod pump on 02/16/05.

RECEIVED

FEB 24 2005

DIV. OF OIL, GAS & MINING

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)

Tara Kinney

Title

Production Clerk

Signature

Tara Kinney

Date

2/21/2005

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)



Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
INLAND PRODUCTION COMPANY

FILED
In the Office of the
Secretary of State of Texas
SEP 02 2004
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs
Susan G. Riggs, Treasurer



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov>



IN REPLY REFER TO:

3106

(UT-924)

September 16, 2004

Memorandum

To: Vernal Field Office

From: Acting Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Michael Coulthard
Acting Chief, Branch of
Fluid Minerals

Enclosure

1. State of Texas Certificate of Registration

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare

| | | | | | |
|---------|--------|--------|--------|-------|--------|
| UTSL- | 15855 | 61052 | 73088 | 76561 | |
| 071572A | 16535 | 62848 | 73089 | 76787 | |
| 065914 | 16539 | 63073B | 73520A | 76808 | |
| | 16544 | 63073D | 74108 | 76813 | |
| | 17036 | 63073E | 74805 | 76954 | 63073X |
| | 17424 | 63073O | 74806 | 76956 | 63098A |
| | 18048 | 64917 | 74807 | 77233 | 68528A |
| UTU- | 18399 | 64379 | 74808 | 77234 | 72086A |
| | 19267 | 64380 | 74389 | 77235 | 72613A |
| 02458 | 26026A | 64381 | 74390 | 77337 | 73520X |
| 03563 | 30096 | 64805 | 74391 | 77338 | 74477X |
| 03563A | 30103 | 64806 | 74392 | 77339 | 75023X |
| 04493 | 31260 | 64917 | 74393 | 77357 | 76189X |
| 05843 | 33992 | 65207 | 74398 | 77359 | 76331X |
| 07978 | 34173 | 65210 | 74399 | 77365 | 76788X |
| 09803 | 34346 | 65635 | 74400 | 77369 | 77098X |
| 017439B | 36442 | 65967 | 74404 | 77370 | 77107X |
| 017985 | 36846 | 65969 | 74405 | 77546 | 77236X |
| 017991 | 38411 | 65970 | 74406 | 77553 | 77376X |
| 017992 | 38428 | 66184 | 74411 | 77554 | 78560X |
| 018073 | 38429 | 66185 | 74805 | 78022 | 79485X |
| 019222 | 38431 | 66191 | 74806 | 79013 | 79641X |
| 020252 | 39713 | 67168 | 74826 | 79014 | 80207X |
| 020252A | 39714 | 67170 | 74827 | 79015 | 81307X |
| 020254 | 40026 | 67208 | 74835 | 79016 | |
| 020255 | 40652 | 67549 | 74868 | 79017 | |
| 020309D | 40894 | 67586 | 74869 | 79831 | |
| 022684A | 41377 | 67845 | 74870 | 79832 | |
| 027345 | 44210 | 68105 | 74872 | 79833 | |
| 034217A | 44426 | 68548 | 74970 | 79831 | |
| 035521 | 44430 | 68618 | 75036 | 79834 | |
| 035521A | 45431 | 69060 | 75037 | 80450 | |
| 038797 | 47171 | 69061 | 75038 | 80915 | |
| 058149 | 49092 | 69744 | 75039 | 81000 | |
| 063597A | 49430 | 70821 | 75075 | | |
| 075174 | 49950 | 72103 | 75078 | | |
| 096547 | 50376 | 72104 | 75089 | | |
| 096550 | 50385 | 72105 | 75090 | | |
| | 50376 | 72106 | 75234 | | |
| | 50750 | 72107 | 75238 | | |
| 10760 | 51081 | 72108 | 76239 | | |
| 11385 | 52013 | 73086 | 76240 | | |
| 13905 | 52018 | 73087 | 76241 | | |
| 15392 | 58546 | 73807 | 76560 | | |

OPERATOR CHANGE WORKSHEET

011

Change of Operator (Well Sold)

Designation of Agent/Operator

ROUTING

1. GLH

2. CDW

3. FILE

X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

9/1/2004

FROM: (Old Operator):

N5160-Inland Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

TO: (New Operator):

N2695-Newfield Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

CA No.

Unit:

WELL(S)

| NAME | SEC | TWN | RNG | API NO | ENTITY NO | LEASE TYPE | WELL TYPE | WELL STATUS | |
|--------------------|-----|------|------|------------|-----------|------------|-----------|-------------|---|
| FEDERAL 16-1-9-17 | 01 | 090S | 170E | 4304735496 | 14481 | Federal | OW | DRL | K |
| FEDERAL 16-11-9-17 | 11 | 090S | 170E | 4304735497 | 99999 | Federal | OW | DRL | K |
| FEDERAL 14-11-9-17 | 11 | 090S | 170E | 4304735498 | | Federal | OW | APD | K |
| FEDERAL 10-11-9-17 | 11 | 090S | 170E | 4304735500 | | Federal | OW | APD | K |
| FEDERAL 8-11-9-17 | 11 | 090S | 170E | 4304735501 | | Federal | OW | DRL | K |
| FEDERAL 2-11-9-17 | 11 | 090S | 170E | 4304735502 | | Federal | OW | DRL | K |
| FEDERAL 16-12-9-17 | 12 | 090S | 170E | 4304735516 | | Federal | OW | DRL | K |
| FEDERAL 14-12-9-17 | 12 | 090S | 170E | 4304735517 | 14500 | Federal | OW | DRL | K |
| FEDERAL 12-12-9-17 | 12 | 090S | 170E | 4304735518 | 14497 | Federal | OW | DRL | K |
| FEDERAL 10-12-9-17 | 12 | 090S | 170E | 4304735519 | 14482 | Federal | OW | DRL | K |
| FEDERAL 4-12-9-17 | 12 | 090S | 170E | 4304735520 | 14553 | Federal | OW | DRL | K |
| FEDERAL 1-4-9-18 | 04 | 090S | 180E | 4304735473 | 14533 | Federal | OW | DRL | K |
| FEDERAL 7-4-9-18 | 04 | 090S | 180E | 4304735474 | 14499 | Federal | OW | DRL | K |
| FEDERAL 9-4-9-18 | 04 | 090S | 180E | 4304735475 | 14530 | Federal | OW | DRL | K |
| FEDERAL 15-4-9-18 | 04 | 090S | 180E | 4304735476 | | Federal | OW | APD | K |
| FEDERAL 14-5-9-18 | 05 | 090S | 180E | 4304735505 | | Federal | OW | APD | K |
| FEDERAL 12-5-9-18 | 05 | 090S | 180E | 4304735506 | | Federal | OW | APD | K |
| FEDERAL 12-7-9-18 | 07 | 090S | 180E | 4304735503 | | Federal | OW | APD | K |
| FEDERAL 8-7-9-18 | 07 | 090S | 180E | 4304735504 | | Federal | OW | APD | K |
| FEDERAL 3-17-9-18 | 17 | 090S | 180E | 4304735560 | | Federal | OW | APD | K |
| | | | | | | | | | |
| | | | | | | | | | |

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/15/20042. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/15/20043. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 2/23/20054. Is the new operator registered in the State of Utah: YES Business Number: 755627-01435. If **NO**, the operator was contacted on:

6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 2/28/2005
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 2/28/2005
3. Bond information entered in RBDMS on: 2/28/2005
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
5. Injection Projects to new operator in RBDMS on: 2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: UT 0056

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 61BSBDH2912

FEE & STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 61BSBDH2919

2. The **FORMER** operator has requested a release of liability from their bond on: n/a*
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05

012

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WORK

OIL WELL ☒ GAS WELL ☐ DRY ☐ Other _____

1b. TYPE OF WELL

NEW WELL ☒ WORK OVER ☐ DEEPEN ☐ PLUG BACK ☐ DIFF RESVR. ☐ Other _____

2. NAME OF OPERATOR

Newfield Exploration Company

3. ADDRESS AND TELEPHONE NO.

1401 17th St. Suite 1000 Denver, CO 80202

4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements.)*

At Surface 1831 FSL & 2068 FWL (NE-SW) Sec. 4, Twp 9S, Rng 18E
At top prod. Interval reported below 1984 FNL 1999 FEL (SWNE)

At total depth

14. API NO.

43-047-35474

DATE ISSUED

2/12/04

12. COUNTY OR PARISH

Utah

13. STATE

UT

15. DATE SPUNDED

1/10/05

16. DATE T.D. REACHED

1/18/05

17. DATE COMPL. (Ready to prod.)

2/16/05

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*

4937' GL

4949' KB

19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD

6010'

21. PLUG BACK T.D., MD & TVD

5955'

22. IF MULTIPLE COMPL., HOW MANY*

23. INTERVALS DRILLED BY

ROTARY TOOLS

X

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)*

Green River 4759'-5747'

25. WAS DIRECTIONAL SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

Dual Induction Guard, SP, Compensated Density, Compensated Neutron, GR, Caliper, Cement Bond Log

27. WAS WELL CORED

No

23. CASING RECORD (Report all strings set in well)

| CASING SIZE/GRADE | WEIGHT, LB/FT. | DEPTH SET (MD) | HOLE SIZE | TOP OF CEMENT, CEMENTING RECORD | AMOUNT PULLED |
|-------------------|----------------|----------------|-----------|-----------------------------------------|---------------|
| 8-5/8" - J-55 | 24# | 306' | 12-1/4" | To surface with 160 sx Class "G" cmt | |
| 5-1/2" - J-55 | 15.5# | 5999' | 7-7/8" | 350 sx Premlite II and 500 sx 50/50 Poz | |

29. LINER RECORD

| SIZE | TOP (MD) | BOTTOM (MD) | SACKS CEMENT* | SCREEN (MD) | SIZE | DEPTH SET (MD) | PACKER SET (MD) |
|------|----------|-------------|---------------|-------------|--------|----------------|-----------------|
| | | | | | 2-7/8" | EOT @ | TA @ |
| | | | | | | 5833' | 5703' |

31. PERFORATION RECORD (Interval, size and number)

| INTERVAL | SIZE | SPF/NUMBER | DEPTH INTERVAL (MD) | AMOUNT AND KIND OF MATERIAL USED |
|----------------------------------|------|------------|---------------------|----------------------------------------------|
| (CP3&2) 5680'-5697', 5722'-5747' | .41" | 4/168 | 5680'-5747' | Frac w/ 90,782# 20/40 sand in 674 bbls fluid |
| (B2) 5137'-5146' | .41" | 4/36 | 5137'-5146' | Frac w/ 30,242# 20/40 sand in 312 bbls fluid |
| (DS3) 4759'-4779' | .41" | 4/80 | 4759'-4779' | Frac w/ 66,758# 20/40 sand in 489 bbls fluid |

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

RECEIVED

MAR 30 2005

DIV. OF OIL, GAS & MINING

33.* PRODUCTION

| | | | | | | | | |
|----------------------------------|-----------------|-----------------------------------------------------------------------------------------------------------------------|------------------------------|-----------------|-----------------|-------------------|-------------------------------------------------|----------------------|
| DATE FIRST PRODUCTION 2/16/05 | | PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) 2-1/2" x 1-1/2" x 14.5' RHAC SM Plunger Pump | | | | | WELL STATUS (Producing or shut-in) PRODUCING | |
| DATE OF TEST 10 day ave | HOURS TESTED | CHOKE SIZE | PROD'N. FOR TEST PERIOD → | OIL--BBL. 38 | GAS--MCF. 34 | WATER--BBL. 17 | | GAS-OIL RATIO 895 |
| FLOW. TUBING PRESS. | CASING PRESSURE | CALCULATED 24-HOUR RATE → | OIL--BBL. | GAS--MCF. | WATER--BBL. | | OIL GRAVITY-API (CORR.) | |

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold & Used for Fuel

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED Krishna Russell
Krishna Russell

TITLE Production Clerk

DATE 3/23/2005

KR

*(See Instructions and Spaces for Additional Data on Reverse Side)

| 37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries); | | | | 38. GEOLOGIC MARKERS | | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|--------|-------------------------------|-----------------------|-------------|------------------|
| FORMATION | TOP | BOTTOM | DESCRIPTION, CONTENTS, ETC. | NAME | TOP | |
| | | | | | MEAS. DEPTH | TRUE VERT. DEPTH |
| | | | Well Name Federal 7-4-9-18 | Garden Gulch Mkr | 3840' | |
| | | | | Garden Gulch 1 | 4013' | |
| | | | | Garden Gulch 2 | 4121' | |
| | | | | Point 3 Mkr | 4387' | |
| | | | | X Mkr | 4612' | |
| | | | | Y-Mkr | 4649' | |
| | | | | Douglas Creek Mkr | 4781' | |
| | | | | BiCarbonate Mkr | 5042' | |
| | | | | B Limestone Mkr | 5194' | |
| | | | | Castle Peak | 5574' | |
| | | | | Basal Carbonate | 5996' | |
| | | | | Total Depth (LOGGERS) | 6015' | |

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

013

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side

5. Lease Serial No.

UTU17424

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

FEDERAL 7-4-9-18

9. API Well No.

4304735474

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State

Uintah, UT

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1984 FNL 1979 FEL

SW/NE Section 4 T9S R18E

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|------------------------------------------------------|----------------------------------------------|-------------------------------------------|---------------------------------------------------|-------------------------------------------|
| <input checked="" type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production(Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Subsequent Report | <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Final Abandonment Notice | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other |
| | <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug & Abandon | <input type="checkbox"/> Temporarily Abandon | Variance |
| | <input type="checkbox"/> Convert to Injector | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Newfield Production Company is requesting a variance from Onshore Order 43 CFR Part 3160 Section 4 requiring production tanks to be equipped with Enardo or equivalent vent line valves. Inland operates wells that produce from the Green River formation, which are relatively low gas producers (20 mcfpd). The majority of the wells are equipped with a three phase separator to maximize gas separation and sales.

Newfield is requesting a variance for safety reasons. Crude oil production tanks equipped with back pressure devices will emit a surge of gas when the thief hatches are open. While gauging tanks, lease operators will be subject to breathing toxic gases as well as risk a fire hazard, under optimum conditions

COPIES SENT TO OPERATOR

By: 4-14-04

Initials: CHD

RECEIVED
APR 08 2005
DIV. OF OIL, GAS & MINING

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)
Mandie Crozier

Title

Regulatory Specialist

Signature

Date

04/07/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Accepted by the
Utah Division of

Federal Approval Of This
Action Is Necessary

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

Date: 4/14/05

By: [Signature]



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155



IN REPLY REFER TO
3180
UT-922

June 30, 2005

Newfield Production Company
Attn: Kelly L. Donohoue
1401 Seventeenth Street, Suite 1000
Denver, Colorado 80202

Gentlemen:

The Sundance (Green River) Unit Agreement, Uintah County, Utah, was approved June 30, 2005. This agreement has been designated No. UTU82472X, and is effective July 1, 2005. The unit area embraces 11,143.86 acres, more or less.

Pursuant to regulations issued and effective June 17, 1988, all operations within the Sundance (Green River) Unit will be covered by your nationwide (Utah) oil and gas bond No. 0056.

The following leases embrace lands included within the unit area:

| | | | |
|------------|-----------|-----------|-----------|
| UTU0075174 | UTU39713 | UTU65970* | UTU79013* |
| UTU16539* | UTU39714 | UTU74404 | UTU79014* |
| UTU16540 | UTU44429 | UTU74835 | UTU80915 |
| UTU17424* | UTU64806* | UTU74872* | UTU82205 |
| UTU18043 | UTU65969 | UTU75234 | |

* Indicates lease to be considered for segregation by the Bureau of Land Management pursuant to Section 18 (g) of the unit agreement and Public Law 86-705.

All lands and interests by State of Utah, Cause No. 228-08 are fully committed.

Approval of this agreement does not warrant or certify that the operator thereof and other holders of operating rights hold legal or equitable title to those rights in the subject leases which are committed hereto.

RECEIVED

JUL 01 2005

DIV. OF OIL, GAS & MINING

*Docket No
2005-009*

We are of the opinion that the agreement is necessary and advisable in the public interest and for the purpose of more properly conserving natural resources. Certification-Determination, signed by the School and Institutional Trust Land Administration for the State of Utah, is attached to the enclosed agreement. We request that you furnish the State of Utah and all other interested principals with appropriate evidence of this approval.

Sincerely,

/s/ Terry Catlin

Terry Catlin
Acting Chief, Branch of Fluid Minerals

Enclosure

bcc: Mary Higgins w/enclosure
MMS - Data Management Division (Attn: James Sykes)
Trust Lands Administration
Division of Oil, Gas and Mining
Field Manager - Vernal w/enclosure
File - Sundance (Green River) Unit w/enclosure
Agr. Sec. Chron
Fluid Chron
Central Files

UT922:TAThompson:tt:06/30/2005

Entity Form 6
"C" Change from one existing entity to another existing entity

| API | Well | Sec | Twsp | Rng | Entity | Entity Eff Date |
|------------|---------------------|-----|------|------|----------------|-----------------|
| 4304735697 | FEDERAL 15-13-9-17 | 13 | 090S | 170E | 14828 to 14844 | 9/20/2005 |
| 4304735698 | FEDERAL 13-13-9-17 | 13 | 090S | 170E | 14813 to 14844 | 9/20/2005 |
| 4304735699 | FEDERAL 11-13-9-17 | 13 | 090S | 170E | 14837 to 14844 | 9/20/2005 |
| 4304735702 | FEDERAL 5-13-9-17 | 13 | 090S | 170E | 14836 to 14844 | 9/20/2005 |
| 4304736012 | FEDERAL 14-13-9-17 | 13 | 090S | 170E | 14790 to 14844 | 9/20/2005 |
| 4304732438 | FEDERAL 44-14Y | 14 | 090S | 170E | 11506 to 14844 | 9/20/2005 |
| 4304735708 | FEDERAL 9-14-9-17 | 14 | 090S | 170E | 14808 to 14844 | 9/20/2005 |
| 4304735709 | FEDERAL 11-14-9-17 | 14 | 090S | 170E | 14734 to 14844 | 9/20/2005 |
| 4304735710 | FEDERAL 15-14-9-17 | 14 | 090S | 170E | 14735 to 14844 | 9/20/2005 |
| 4304736068 | FEDERAL 14-14-9-17 | 14 | 090S | 170E | 14770 to 14844 | 9/20/2005 |
| 4304736069 | FEDERAL 10-14-9-17 | 14 | 090S | 170E | 14787 to 14844 | 9/20/2005 |
| 4304736071 | FEDERAL 6-14-9-17 | 14 | 090S | 170E | 14809 to 14844 | 9/20/2005 |
| 4304731181 | FEDERAL 14-4-9-18 | 04 | 090S | 180E | 14601 to 14844 | 9/20/2005 |
| 4304732653 | FEDERAL 13-4-9-18 | 04 | 090S | 180E | 14602 to 14844 | 9/20/2005 |
| 4304732654 | FEDERAL 11-4-9-18 | 04 | 090S | 180E | 14603 to 14844 | 9/20/2005 |
| 4304735473 | FEDERAL 1-4-9-18 | 04 | 090S | 180E | 14533 to 14844 | 9/20/2005 |
| 4304735474 | FEDERAL 7-4-9-18 | 04 | 090S | 180E | 14499 to 14844 | 9/20/2005 |
| 4304735475 | FEDERAL 9-4-9-18 | 04 | 090S | 180E | 14530 to 14844 | 9/20/2005 |
| 4304735589 | FEDERAL 2-4-9-18 | 04 | 090S | 180E | 14485 to 14844 | 9/20/2005 |
| 4304735590 | FEDERAL 3-4-9-18 | 04 | 090S | 180E | 14697 to 14844 | 9/20/2005 |
| 4304735591 | FEDERAL 5-4-9-18 | 04 | 090S | 180E | 14680 to 14844 | 9/20/2005 |
| 4304735592 | FEDERAL 6-4-9-18 | 04 | 090S | 180E | 14696 to 14844 | 9/20/2005 |
| 4304735593 | FEDERAL 8-4-9-18 | 04 | 090S | 180E | 14528 to 14844 | 9/20/2005 |
| 4304735594 | FEDERAL 10-4-9-18 | 04 | 090S | 180E | 14535 to 14844 | 9/20/2005 |
| 4304735595 | FEDERAL 12-4-9-18 | 04 | 090S | 180E | 14670 to 14844 | 9/20/2005 |
| 4304732503 | 21BALCRON FED 31-5Y | 05 | 090S | 180E | 11680 to 14844 | 9/20/2005 |
| 4304735290 | FEDERAL 5-5-9-18 | 05 | 090S | 180E | 14669 to 14844 | 9/20/2005 |
| 4304735292 | FEDERAL 9-5-9-18 | 05 | 090S | 180E | 14554 to 14844 | 9/20/2005 |
| 4304735293 | FEDERAL 11-5-9-18 | 05 | 090S | 180E | 14769 to 14844 | 9/20/2005 |
| 4304735294 | FEDERAL 13-5-9-18 | 05 | 090S | 180E | 14658 to 14844 | 9/20/2005 |
| 4304735505 | FEDERAL 14-5-9-18 | 05 | 090S | 180E | 14687 to 14844 | 9/20/2005 |
| 4304735506 | FEDERAL 12-5-9-18 | 05 | 090S | 180E | 14651 to 14844 | 9/20/2005 |
| 4304735891 | FEDERAL 10-5-9-18 | 05 | 090S | 180E | 14698 to 14844 | 9/20/2005 |
| 4304734933 | FEDERAL 6-6-9-18 | 06 | 090S | 180E | 14152 to 14844 | 9/20/2005 |
| 4304734934 | FEDERAL 7-6-9-18 | 06 | 090S | 180E | 14126 to 14844 | 9/20/2005 |
| 4304734936 | FEDERAL 13-6-9-18 | 06 | 090S | 180E | 14049 to 14844 | 9/20/2005 |



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8

999 18th STREET - SUITE 300

DENVER, CO 80202-2466

<http://www.epa.gov/region08>

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

SEP 21 2006

David Gerbig
Newfield Production Company
1401 Seventeenth Street
Suite 1000
Denver, CO 80202

Accepted by the
Utah Division of
Oil, Gas and Mining

FOR RECORD ONLY

43.047.35474

9S 19E 4

Re: Underground Injection Control Program
Final Permit: Federal 7-4-9-18
Uintah County, Utah
EPA Permit No. UT21039-07060

Dear Mr. Gerbig:

Enclosed is your copy of the FINAL Underground Injection Control (UIC) Permit for the proposed Federal 7-4-9-18 injection well. A Statement of Basis, which discusses development of the conditions and requirements of the Permit, also is included.

The Public Comment period ended on SEP 21 2006. There were no comments on the Draft Permit received during the Public Notice period, and therefore the Final Permit becomes effective on the date of issuance. All conditions set forth herein refer to Title 40 Parts 124, 144, 146, and 147 of the Code of Federal Regulations (CFR) and are regulations that are in effect on the date that this Permit becomes effective.

Please note that under the terms of the Final Permit, you are authorized only to construct the proposed injection well, and must fulfill the "Prior to Commencing Injection" requirements of the Permit, Part II Section C Subpart 1 and obtain written Authorization to Inject prior to commencing injection. It is your responsibility to be familiar with and to comply with all provisions of the Final Permit.

The Permit and the authorization to inject are issued for the operating life of the well unless terminated (Part III, Section B). The EPA will review this Permit at least every five (5) years to determine whether action under 40 CFR § 144.36(a) is warranted.

RECEIVED


OCT 02 2006



DIV. OF OIL, GAS & MINING
Printed on Recycled Paper

If you have any questions on the enclosed Final Permit or Statement of Basis, please call Emmett Schmitz of my staff at (303) 312-6174, or toll-free at (800) 227-8917, ext. 6174.

Sincerely,



for Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

enclosure: Final UIC Permit
Statement of Basis
Form 7520-7 Application to Transfer Permit
Form 7520-10 Completion Report
Form 7520-11 Monitoring Report
Form 7520-12 Well Rework Record
Form 7520-13 Plugging Record
Groundwater Section Guidance 35
Groundwater Section Guidance 37
Groundwater Section Guidance 39

cc: Letter only:

Maxine Natchees
Acting Chairperson
Uintah & Ouray Business Committee
Ute Indian Tribe

Chester Mills
Superintendent
U.S. Bureau of Indian Affairs
Uintah & Ouray Indian Agency

Final Permit & Statement of Basis:

S. Elaine Willie
Environmental Coordinator
Ute Indian Tribe



Lynn Becker
Director
Energy & Minerals Dept.
Ute Indian Tribe

Gilbert Hunt
Associate Director
State of Utah - Natural Resources

Fluid Minerals Engineering Office
U.S. Bureau of Land Management
Vernal, Utah

all enclosures:

Michael Guinn
Vice President - Operations
Newfield Production Company
Myton, Utah





**UNDERGROUND INJECTION CONTROL PROGRAM
PERMIT**

PREPARED: September 2006

Permit No. UT21039-07060

Class II Enhanced Oil Recovery Injection Well

**Federal 7-4-9-18
Uintah County, UT**

Issued To

Newfield Production Company

1401 Seventeenth Street

Suite 1000

Denver, CO 80202

RECEIVED

OCT 02 2006

DIV. OF OIL, GAS & MINING

Part I. AUTHORIZATION TO CONSTRUCT AND OPERATE

Under the authority of the Safe Drinking Water Act and Underground Injection Control (UIC) Program regulations of the U. S. Environmental Protection Agency (EPA) codified at Title 40 of the Code of Federal Regulations (40 CFR) Parts 2, 124, 144, 146, and 147, and according to the terms of this Permit,

Newfield Production Company
1401 Seventeenth Street
Suite 1000
Denver, CO 80202

is authorized to construct and to operate the following Class II injection well or wells:

Federal 7-4-9-18
1984' FNL & 1979' FEL, SWNE S4, T9S, R18E
Uintah County, UT


Permit requirements herein are based on regulations found in 40 CFR Parts 124, 144, 146, and 147 which are in effect on the Effective Date of this Permit. Issuance of this Permit does not convey any property rights of any sort, nor does it authorize any injury to persons or property or invasion of other private rights, or any infringement of other federal, State or local law or regulation.

This Permit is based on representations made by the applicant and on other information contained in the Administrative Record. Misrepresentation of information or failure to fully disclose all relevant information may be cause for termination, revocation and reissuance, or modification of this Permit and/or formal enforcement action. This Permit will be reviewed periodically to determine whether action under 40 CFR 144.36(a) is required.

This Permit is issued for the life of the well or wells unless modified, revoked and reissued, or terminated under 40 CFR 144.39 or 144.40. This Permit may be adopted, modified, revoked and reissued, or terminated if primary enforcement authority for this program is delegated to an Indian Tribe or a State. Upon the effective date of delegation, all reports, notifications, questions and other compliance actions shall be directed to the Indian tribe or State Program Director or designee.

Issue Date: SEP 21 2006

Effective Date SEP 21 2006


for Stephen S. Tuber
Assistant Regional Administrator*
Office of Partnerships and Regulatory Assistance

*NOTE: The person holding this title is referred to as the "Director" throughout this Permit.

PART II. SPECIFIC PERMIT CONDITIONS

Section A. WELL CONSTRUCTION REQUIREMENTS

These requirements represent the approved minimum construction standards for well casing and cement, injection tubing, and packer.

Details of the approved well construction plan are incorporated into this Permit as APPENDIX A. Changes to the approved plan that may occur during construction must be approved by the Director prior to being physically incorporated.

1. Casing and Cement.

The well or wells shall be cased and cemented to prevent the movement of fluids into or between underground sources of drinking water. The well casing and cement shall be designed for the life expectancy of the well and of the grade and size shown in APPENDIX A. Remedial cementing may be required if shown to be inadequate by cement bond log or other attempted demonstration of Part II (External) mechanical integrity.

2. Injection Tubing and Packer.

Injection tubing is required, and shall be run and set with a packer at or below the depth indicated in APPENDIX A. The packer setting depth may be changed provided it remains below the depth indicated in APPENDIX A and the Permittee provides notice and obtains the Director's approval for the change.

3. Sampling and Monitoring Devices.

The Permittee shall install and maintain in good operating condition:

- (a) a "tap" at a conveniently accessible location on the injection flow line between the pump house or storage tanks and the injection well, isolated by shut-off valves, for collection of representative samples of the injected fluid; and
- (b) one-half (1/2) inch female iron pipe fitting, isolated by shut-off valves and located at the wellhead at a conveniently accessible location, for the attachment of a pressure gauge capable of monitoring pressures ranging from normal operating pressures up to the Maximum Allowable Injection Pressure specified in APPENDIX C:
 - (i) on the injection tubing; and
 - (ii) on the tubing-casing annulus (TCA); and
- (c) a pressure actuated shut-off device attached to the injection flow line set to shut-off the injection pump when or before the Maximum Allowable Injection Pressure specified in APPENDIX C is reached at the wellhead; and
- (d) a non-resettable cumulative volume recorder attached to the injection line.

4. Well Logging and Testing

Well logging and testing requirements are found in APPENDIX B. The Permittee shall ensure the log and test requirements are performed within the time frames specified in APPENDIX B. Well logs and tests shall be performed according to current EPA-approved procedures. Well log and test results shall be submitted to the Director within sixty (60) days of completion of the logging or testing activity, and shall include a report describing the methods used during logging or testing and an interpretation of the test or log results.

5. Postponement of Construction or Conversion

The Permittee shall complete well construction within one year of the Effective Date of the Permit, or in the case of an Area Permit within one year of authorization of the additional well. Authorization to construct and operate shall expire if the well has not been constructed within one year of the Effective Date of the Permit or authorization and the Permit may be terminated under 40 CFR 144.40, unless the Permittee has notified the Director and requested an extension prior to expiration. Notification shall be in writing, and shall state the reasons for the delay and provide an estimated completion date. Once Authorization has expired under this part, the complete permit process including opportunity for public comment may be required before Authorization to construct and operate may be reissued.

6. Workovers and Alterations

Workovers and alterations shall meet all conditions of the Permit. Prior to beginning any addition or physical alteration to an injection well that may significantly affect the tubing, packer or casing, the Permittee shall give advance notice to the Director and obtain the Director's approval. The Permittee shall record all changes to well construction on a Well Rework Record (EPA Form 7520-12), and shall provide this and any other record of well workover, logging, or test data to EPA within sixty (60) days of completion of the activity.

A successful demonstration of Part I MI is required following the completion of any well workover or alteration which affects the casing, tubing, or packer. Injection operations shall not be resumed until the well has successfully demonstrated mechanical integrity and the Director has provided written approval to resume injection.

Section B. MECHANICAL INTEGRITY

The Permittee is required to ensure each injection well maintains mechanical integrity at all times. The Director, by written notice, may require the Permittee to comply with a schedule describing when mechanical integrity demonstrations shall be made.

An injection well has mechanical integrity if:

- (a) There is no significant leak in the casing, tubing, or packer (Part I); and
- (b) There is no significant fluid movement into an underground source of drinking water through vertical channels adjacent to the injection well bore (Part II).

1. Demonstration of Mechanical Integrity (MI).

The operator shall demonstrate MI prior to commencing injection and periodically thereafter. Well-specific conditions dictate the methods and the frequency for demonstrating MI and are discussed in the Statement of Basis. The logs and tests are designed to demonstrate both internal (Part I) and external (Part II) MI as described above. The conditions present at this well site warrant the methods and frequency required in Appendix B of this Permit.

In addition to these regularly scheduled demonstrations of MI, the operator shall demonstrate internal (Part I) MI after any workover which affects the tubing, packer or casing.

The Director may require additional or alternative tests if the results presented by the operator are not satisfactory to the Director to demonstrate there is no movement of fluid into or between USDWs resulting from injection activity. Results of MI tests shall be submitted to the Director as soon as possible but no later than sixty (60) days after the test is complete.

2. Mechanical Integrity Test Methods and Criteria

EPA-approved methods shall be used to demonstrate mechanical integrity. Ground Water Section Guidance No. 34 "Cement Bond Logging Techniques and Interpretation", Ground Water Section Guidance No. 37, "Demonstrating Part II (External) Mechanical Integrity for a Class II injection well permit", and Ground Water Section Guidance No. 39, "Pressure Testing Injection Wells for Part I (Internal) Mechanical Integrity" are available from EPA and will be provided upon request.

The Director may stipulate specific test methods and criteria best suited for a specific well construction and injection operation.

3. Notification Prior to Testing.

The Permittee shall notify the Director at least 30 days prior to any scheduled mechanical integrity test. The Director may allow a shorter notification period if it would be sufficient to enable EPA to witness the mechanical integrity test. Notification may be in the form of a yearly or quarterly schedule of planned mechanical integrity tests, or it may be on an individual basis.

4. Loss of Mechanical Integrity.

If the well fails to demonstrate mechanical integrity during a test, or a loss of mechanical integrity becomes evident during operation (such as presence of pressure in the TCA, water flowing at the surface, etc.), the Permittee shall notify the Director within 24 hours (see Part III Section E Paragraph 11(e) of this Permit) and the well shall be shut-in within 48 hours unless the Director requires immediate shut-in.

Within five days, the Permittee shall submit a follow-up written report that documents test results, repairs undertaken or a proposed remedial action plan.

Injection operations shall not be resumed until after the well has successfully been repaired and demonstrated mechanical integrity, and the Director has provided approval to resume injection.

Section C. WELL OPERATION

INJECTION BETWEEN THE OUTERMOST CASING PROTECTING UNDERGROUND SOURCES OF DRINKING WATER AND THE WELL BORE IS PROHIBITED.

Injection is approved under the following conditions:

1. Requirements Prior to Commencing Injection.

Well injection, including for new wells authorized by an Area Permit under 40 CFR 144.33 (c), may commence only after all well construction and pre-injection requirements herein have been met and approved. The Permittee may not commence injection until construction is complete, and

- (a) The Permittee has submitted to the Director a notice of completion of construction and a completed EPA Form 7520-10 or 7520-12; all applicable logging and testing requirements of this Permit (see APPENDIX B) have been fulfilled and the records submitted to the Director; mechanical integrity pursuant to 40 CFR 146.8 and Part II Section B of this Permit has been demonstrated; and
 - (i) The Director has inspected or otherwise reviewed the new injection well and finds it is in compliance with the conditions of the Permit; or
 - (ii) The Permittee has not received notice from the Director of his or her intent to inspect or otherwise review the new injection well within 13 days of the date of the notice in Paragraph 1a, in which case prior inspection or review is waived and the Permittee may commence injection.

2. Injection Interval.

Injection is permitted only within the approved injection interval, listed in APPENDIX C. Additional individual injection perforations may be added provided that they remain within the approved injection interval and the Permittee provides notice to the Director in accordance with Part II, Section A, Paragraph 6.

3. Injection Pressure Limitation

- (a) The permitted Maximum Allowable Injection Pressure (MAIP), measured at the wellhead, is found in APPENDIX C. Injection pressure shall not exceed the amount the Director determines is appropriate to ensure that injection does not initiate new fractures or propagate existing fractures in the confining zone adjacent to USDWs. In no case shall injection pressure cause the movement of injection or formation fluids into a USDW.
- (b) The Permittee may request a change of the MAIP, or the MAIP may be increased or decreased by the Director in order to ensure that the requirements in Paragraph (a) above are fulfilled. The Permittee may be required to conduct a step rate injection test or other suitable test to provide information for determining the fracture pressure of the injection zone. Change of the permitted MAIP by the Director shall be by modification of this Permit and APPENDIX C.

4. Injection Volume Limitation.

Injection volume is limited to the total volume specified in APPENDIX C.

5. Injection Fluid Limitation.

Injected fluids are limited to those identified in 40 CFR 144.6(b)(2) as fluids used for enhanced recovery of oil or natural gas, including those which are brought to the surface in connection with conventional oil or natural gas production that may be commingled with waste waters from gas plants which are an integral part of production operations unless those waters are classified as a hazardous waste at the time of injection, pursuant to 40 CFR 144.6(b). Non-exempt wastes, including unused fracturing fluids or acids, gas plant cooling tower cleaning wastes, service wastes and vacuum truck wastes, are NOT approved for injection. This well is NOT approved for commercial brine injection, industrial waste fluid disposal or injection of hazardous waste as defined by CFR 40 Part 261. The Permittee shall provide a listing of the sources of injected fluids in accordance with the reporting requirements in Part II Section D Paragraph 4 and APPENDIX D of this Permit.

6. Tubing-Casing Annulus (TCA)

The tubing-casing annulus (TCA) shall be filled with water treated with a corrosion inhibitor, or other fluid approved by the Director. The TCA valve shall remain closed during normal operating conditions and the TCA pressure shall be maintained at zero (0) psi.

If TCA pressure cannot be maintained at zero (0) psi, the Permittee shall follow the procedures in Ground Water Section Guidance No. 35 "Procedures to follow when excessive annular pressure is observed on a well."

Section D. MONITORING, RECORDKEEPING, AND REPORTING OF RESULTS

1. Monitoring Parameters, Frequency, Records and Reports.

Monitoring parameters are specified in APPENDIX D. Pressure monitoring recordings shall be taken at the wellhead. The listed parameters are to be monitored, recorded and reported at the frequency indicated in APPENDIX D even during periods when the well is not operating.

Monitoring records must include:

- (a) the date, time, exact place and the results of the observation, sampling, measurement, or analysis, and;
- (b) the name of the individual(s) who performed the observation, sampling, measurement, or analysis, and;
- (c) the analytical techniques or methods used for analysis.

2. Monitoring Methods.

- (a) Monitoring observations, measurements, samples, etc. taken for the purpose of complying with these requirements shall be representative of the activity or condition being monitored.

- (b) Methods used to monitor the nature of the injected fluids must comply with analytical methods cited and described in Table 1 of 40 CFR 136.3 or Appendix III of 40 CFR 261, or by other methods that have been approved in writing by the Director.
- (c) Injection pressure, annulus pressure, injection rate, and cumulative injected volumes shall be observed and recorded at the wellhead under normal operating conditions, and all parameters shall be observed simultaneously to provide a clear depiction of well operation.
- (d) Pressures are to be measured in pounds per square inch (psi).
- (e) Fluid volumes are to be measured in standard oil field barrels (bbl).
- (f) Fluid rates are to be measured in barrels per day (bbl/day).

3. Records Retention.

- (a) Records of calibration and maintenance, and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this permit, and records of all data used to complete the application for this permit shall be retained for a period of AT LEAST THREE (3) YEARS from the date of the sample, measurement, report, or application. This period may be extended anytime prior to its expiration by request of the Director.
- (b) Records of the nature and composition of all injected fluids must be retained until three (3) years after the completion of any plugging and abandonment (P&A) procedures specified under 40 CFR 144.52(a)(6) or under Part 146 Subpart G, as appropriate. The Director may require the Permittee to deliver the records to the Director at the conclusion of the retention period. The Permittee shall continue to retain the records after the three (3) year retention period unless the Permittee delivers the records to the Director or obtains written approval from the Director to discard the records.
- (c) The Permittee shall retain records at the location designated in APPENDIX D.

4. Annual Reports.

Whether the well is operating or not, the Permittee shall submit an Annual Report to the Director that summarizes the results of the monitoring required by Part II Section D and APPENDIX D.

The first Annual Report shall cover the period from the effective date of the Permit through December 31 of that year. Subsequent Annual Reports shall cover the period from January 1 through December 31 of the reporting year. Annual Reports shall be submitted by February 15 of the year following data collection. EPA Form 7520-11 may be copied and shall be used to submit the Annual Report, however, the monitoring requirements specified in this Permit are mandatory even if EPA Form 7520-11 indicates otherwise.

Section E. PLUGGING AND ABANDONMENT

1. Notification of Well Abandonment, Conversion or Closure.

The Permittee shall notify the Director in writing at least forty-five (45) days prior to: 1) plugging and abandoning an injection well, 2) converting to a non-injection well, and 3) in the case of an Area Permit, before closure of the project.

2. Well Plugging Requirements

Prior to abandonment, the injection well shall be plugged with cement in a manner which prevents the movement of fluids into or between underground sources of drinking water. Prior to placement of the cement plug(s) the well shall be in a state of static equilibrium with the mud weight equalized top to bottom, either by circulating the mud in the well at least once or by a comparable method prescribed by the Director. The well shall be plugged in accordance with the approved plugging and abandonment plan and with 40 CFR 146.10.

3. Approved Plugging and Abandonment Plan.

The approved plugging and abandonment plan is incorporated into this Permit as APPENDIX E. Changes to the approved plugging and abandonment plan must be approved by the Director prior to beginning plugging operations. The Director also may require revision of the approved plugging and abandonment plan at any time prior to plugging the well.

4. Forty Five (45) Day Notice of Plugging and Abandonment.

The Permittee shall notify the Director at least forty-five (45) days prior to plugging and abandoning a well and provide notice of any anticipated change to the approved plugging and abandonment plan.

5. Plugging and Abandonment Report.

Within sixty (60) days after plugging a well, the Permittee shall submit a report (EPA Form 7520-13) to the Director. The plugging report shall be certified as accurate by the person who performed the plugging operation. Such report shall consist of either:

- (a) A statement that the well was plugged in accordance with the approved plugging and abandonment plan; or
- (b) Where actual plugging differed from the approved plugging and abandonment plan, an updated version of the plan, on the form supplied by the Director, specifying the differences.

6. Inactive Wells.

After any period of two years during which there is no injection the Permittee shall plug and abandon the well in accordance with Part II Section E Paragraph 2 of this Permit unless the Permittee:

- (a) Provides written notice to the Director;
- (b) Describes the actions or procedures the Permittee will take to ensure that the well will not endanger USDWs during the period of inactivity. These actions and procedures shall include compliance with mechanical integrity demonstration, Financial Responsibility and all other permit requirements designed to protect USDWs; and

- (c) Receives written notice by the Director temporarily waiving plugging and abandonment requirements.

PART III. CONDITIONS APPLICABLE TO ALL PERMITS

Section A. EFFECT OF PERMIT

The Permittee is allowed to engage in underground injection in accordance with the conditions of this Permit. The Permittee shall not construct, operate, maintain, convert, plug, abandon, or conduct any other activity in a manner that allows the movement of fluid containing any contaminant into underground sources of drinking water, if the presence of that contaminant may cause a violation of any primary drinking water regulation under 40 CFR 142 or may otherwise adversely affect the health of persons. Any underground injection activity not authorized by this Permit or by rule is prohibited. Issuance of this Permit does not convey property rights of any sort or any exclusive privilege; nor does it authorize any injury to persons or property, any invasion of other private rights, or any infringement of State or local law or regulations. Compliance with the terms of this Permit does not constitute a defense to any enforcement action brought under the provisions of Section 1431 of the Safe Drinking Water Act (SDWA) or any other law governing protection of public health or the environment, for any imminent and substantial endangerment to human health or the environment, nor does it serve as a shield to the Permittee's independent obligation to comply with all UIC regulations. Nothing in this Permit relieves the Permittee of any duties under applicable regulations.

Section B. CHANGES TO PERMIT CONDITIONS

1. Modification, Reissuance, or Termination.

The Director may, for cause or upon a request from the Permittee, modify, revoke and reissue, or terminate this Permit in accordance with 40 CFR 124.5, 144.12, 144.39, and 144.40. Also, this Permit is subject to minor modification for causes as specified in 40 CFR 144.41. The filing of a request for modification, revocation and reissuance, termination, or the notification of planned changes or anticipated noncompliance on the part of the Permittee does not stay the applicability or enforceability of any condition of this Permit.

2. Conversions.

The Director may, for cause or upon a written request from the Permittee, allow conversion of the well from a Class II injection well to a non-Class II well. Conversion may not proceed until the Permittee receives written approval from the Director. Conditions of such conversion may include but are not limited to, approval of the proposed well rework, follow up demonstration of mechanical integrity, well-specific monitoring and reporting following the conversion, and demonstration of practical use of the converted configuration.

3. Transfer of Permit.

Under 40 CFR 144.38, this Permit is transferable provided the current Permittee notifies the Director at least thirty (30) days in advance of the proposed transfer date (EPA Form 7520-7) and provides a written agreement between the existing and new Permittees containing a specific date for transfer of Permit responsibility, coverage and liability between them. The notice shall adequately demonstrate that the financial responsibility requirements of 40 CFR 144.52(a)(7) will be met by the new Permittee. The Director may require modification or revocation and reissuance of the Permit to change the name of the Permittee and incorporate such other requirements as may be necessary under the Safe Drinking Water Act; in some cases, modification or revocation and reissuance is mandatory.

4. Permittee Change of Address.

Upon the Permittee's change of address, or whenever the operator changes the address where monitoring records are kept, the Permittee must provide written notice to the Director within 30 days.

5. Construction Changes, Workovers, Logging and Testing Data

The Permittee shall give advance notice to the Director, and shall obtain the Director's written approval prior to any physical alterations or additions to the permitted facility. Alterations or workovers shall meet all conditions as set forth in this permit. The Permittee shall record any changes to the well construction on a Well Rework Record (EPA Form 7520-12), and shall provide this and any other record of well workovers, logging, or test data to EPA within sixty (60) days of completion of the activity.

Following the completion of any well workovers or alterations which affect the casing, tubing, or packer, a successful demonstration of mechanical integrity (Part III, Section F of this permit) shall be made, and written authorization from the Director received, prior to resuming injection activities.

Section C. SEVERABILITY

The Provisions of this Permit are severable, and if any provision of this Permit or the application of any provision of this Permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this Permit shall not be affected thereby.

Section D. CONFIDENTIALITY

In accordance with 40 CFR Part 2 and 40 CFR 144.5, information submitted to EPA pursuant to this Permit may be claimed as confidential by the submitter. Any such claim must be asserted at the time of submission by stamping the words "confidential business information" on each page containing such information. If no claim is made at the time of submission, EPA may make the information available to the public without further notice. If a claim is asserted, the validity of the claim will be assessed in accordance with the procedures in 40 CFR Part 2 (Public Information). Claims of confidentiality for the following information will be denied:

- The name and address of the Permittee, and
- information which deals with the existence, absence or level of contaminants in drinking water.

Section E. GENERAL PERMIT REQUIREMENTS

1. Duty to Comply.

The Permittee must comply with all conditions of this Permit. Any noncompliance constitutes a violation of the Safe Drinking Water Act (SDWA) and is grounds for enforcement action; for Permit termination, revocation and reissuance, or modification; or for denial of a permit renewal application; except that the Permittee need not comply with the provisions of this Permit to the extent and for the duration such noncompliance is authorized in an emergency permit under 40 CFR 144.34. All violations of the SDWA may subject the Permittee to penalties and/or criminal prosecution as specified in Section 1423 of the SDWA.

2. Duty to Reapply.

If the Permittee wishes to continue an activity regulated by this Permit after the expiration date of this Permit, under 40 CFR 144.37 the Permittee must apply for a new permit prior to the expiration date.

3. Need to Halt or Reduce Activity Not a Defense.

It shall not be a defense for a Permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this Permit.

4. Duty to Mitigate.

The Permittee shall take all reasonable steps to minimize or correct any adverse impact on the environment resulting from noncompliance with this Permit.

5. Proper Operation and Maintenance.

The Permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the Permittee to achieve compliance with the conditions of this Permit. Proper operation and maintenance includes effective performance, adequate funding, adequate operator staffing and training, and adequate laboratory and process controls, including appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems only when necessary to achieve compliance with the conditions of this Permit.

6. Permit Actions.

This Permit may be modified, revoked and reissued or terminated for cause. The filing of a request by the Permittee for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.

7. Property Rights.

This Permit does not convey any property rights of any sort, or any exclusive privilege.

8. Duty to Provide Information.

The Permittee shall furnish to the Director, within a time specified, any information which the Director may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit, or to determine compliance with this permit. The Permittee shall also furnish to the Director, upon request, copies of records required to be kept by this Permit. The Permittee is required to submit any information required by this Permit or by the Director to the mailing address designated in writing by the Director.

9. Inspection and Entry.

The Permittee shall allow the Director, or an authorized representative, upon the presentation of credentials and other documents as may be required by law, to:

- (a) Enter upon the Permittee's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of this Permit;

- (b) Have access to and copy, at reasonable times, any records that must be kept under the conditions of this Permit;
- (c) Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this Permit; and,
- (d) Sample or monitor at reasonable times, for the purpose of assuring permit compliance or as otherwise authorized by the SDWA, any substances or parameters at any location.

10. Signatory Requirements.

All applications, reports or other information submitted to the Director shall be signed and certified according to 40 CFR 144.32. This section explains the requirements for persons duly authorized to sign documents, and provides wording for required certification.

11. Reporting Requirements.

- (a) **Planned changes.** The Permittee shall give notice to the Director as soon as possible of any planned changes, physical alterations or additions to the permitted facility, and prior to commencing such changes.
- (b) **Anticipated noncompliance.** The Permittee shall give advance notice to the Director of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.
- (c) **Monitoring Reports.** Monitoring results shall be reported at the intervals specified in this Permit.
- (d) **Compliance schedules.** Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this Permit shall be submitted no later than 30 days following each schedule date.
- (e) **Twenty-four hour reporting.** The Permittee shall report to the Director any noncompliance which may endanger human health or the environment, including:
 - (i) Any monitoring or other information which indicates that any contaminant may cause endangerment to a USDW; or
 - (ii) Any noncompliance with a permit condition or malfunction of the injection system which may cause fluid migration into or between USDWs.

Information shall be provided, either directly or by leaving a message, within twenty-four (24) hours from the time the permittee becomes aware of the circumstances by telephoning (800) 227-8917 and requesting EPA Region VIII UIC Program Compliance and Technical Enforcement Director, or by contacting the EPA Region VIII Emergency Operations Center at (303) 293-1788.

In addition, a follow up written report shall be provided to the Director within five (5) days of the time the Permittee becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause, the period of noncompliance including exact dates and times, and if the noncompliance has not been corrected the anticipated time it is expected to continue; and the steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance.

- (f) Oil Spill and Chemical Release Reporting: The Permittee shall comply with all reporting requirements related to the occurrence of oil spills and chemical releases by contacting the National Response Center (NRC) at (800) 424-8802, (202) 267-2675, or through the NRC website <http://www.nrc.uscg.mil/index.htm>.
- (g) Other Noncompliance. The Permittee shall report all instances of noncompliance not reported under paragraphs Part III, Section E Paragraph 11(b) or Section E, Paragraph 11(e) at the time the monitoring reports are submitted. The reports shall contain the information listed in Paragraph 11(e) of this Section.
- (h) Other information. Where the Permittee becomes aware that it failed to submit any relevant facts in the permit application, or submitted incorrect information in a permit application or in any report to the Director, the Permittee shall promptly submit such facts or information to the Director.

Section F. FINANCIAL RESPONSIBILITY

1. Method of Providing Financial Responsibility.

The Permittee shall maintain continuous compliance with the requirement to maintain financial responsibility and resources to close, plug, and abandon the underground injection well(s). No substitution of a demonstration of financial responsibility shall become effective until the Permittee receives written notification from the Director that the alternative demonstration of financial responsibility is acceptable. The Director may, on a periodic basis, require the holder of a permit to revise the estimate of the resources needed to plug and abandon the well to reflect changes in such costs and may require the Permittee to provide a revised demonstration of financial responsibility.

2. Insolvency.

In the event of:

- (a) the bankruptcy of the trustee or issuing institution of the financial mechanism; or
- (b) suspension or revocation of the authority of the trustee institution to act as trustee; or

- (c) the institution issuing the financial mechanism losing its authority to issue such an instrument

the Permittee must notify the Director in writing, within ten (10) business days, and the Permittee must establish other financial assurance or liability coverage acceptable to the Director within sixty (60) days after any event specified in (a), (b), or (c) above.

The Permittee must also notify the Director by certified mail of the commencement of voluntary or involuntary proceedings under Title 11 (Bankruptcy), U.S. Code naming the owner or operator as debtor, within ten (10) business days after the commencement of the proceeding. A guarantor, if named as debtor of a corporate guarantee, must make such a notification as required under the terms of the guarantee.

APPENDIX A

WELL CONSTRUCTION REQUIREMENTS

See diagram.

The Federal No. 7-4-9-18 was drilled to a total depth of 6010 (KB) feet in the Basal Carbonate Member of the Green River Formation.

Surface casing (8-5/8 inch) was set at a depth of 306.39 feet (KB) in a 12-1/4 inch hole using 160 sacks of Class "G" cement which was circulated to the surface.

Production casing (5-1/2 inch) was set at a depth of 5998.71 feet (KB) in a 7-7/8 inch hole with 350 sacks of Premium Lite II and 500 sacks of 50/50 poz mix. This well construction is considered adequate to protect USDW's.

The EPA calculates the top of cement as 501 feet from the surface.

The schematic diagram shows the proposed current injection perforations in the Garden Gulch and Douglas Creek Members of the Green River Formation. Additional perforations may be added at a later time between the depths of 3788 feet and the top of the Wasatch Formation (Estimated to be 6020 feet) provided the operator first notifies the Director and later submits an updated well completion report (EPA Form 7520-12) and schematic diagram.

The packer will be required to be set no higher than 100 feet above the top perforation.

Federal 7-4-9-18

Spud Date: 1/10/05

Put on Production: 2/16/05

GL: 4937' KB: 4949'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts. (296.39')

DEPTH LANDED: 306.39' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs Class "G" cmt, est 6 bbls cmt to surf.

Proposed Injection Wellbore Diagram

Initial Production: 38BOPD,
34MCFD, 17BWPD

FRAC JOB

02/10/05 5680'-5747'

Frac CP 3,2 sands as follows:
90,782# 20/40 sand in 674 bbls Lightning
Frac 17 fluid. Treated @ avg press of 1570 psi
w/avg rate of 25.1 BPM. ISIP 1610 psi. Calc
flush: 5678 gal. Actual flush: 5670 gal.

02/10/05 5137'-5146'

Frac B2 sands as follows:
30,242# 20/40 sand in 312 bbls Lightning
Frac 17 fluid. Treated @ avg press of 24.9 psi
w/avg rate of 24.9 BPM. ISIP 2220 psi. Calc
flush: 5135 gal. Actual flush: 5124 gal.

02/10/05 4759'-4779'

Frac DS3 sands as follows:
66,758# 20/40 sand in 489 bbls Lightning
Frac 17 fluid. Treated @ avg press of 1986 psi
w/avg rate of 25 BPM. ISIP 2000 psi. Calc
flush: 4757 gal. Actual flush: 4662 gal.

EPA/TOC

501'

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 140 jts. (5996.71')

DEPTH LANDED: 5998.71' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 350 sxs Prem. Lite II mixed & 500 sxs 50/50 POZ.

CEMENT TOP AT: 350'

80% Bond

*{ 3481' -
3662' -*

306'

-2172' Green River

*-3650' - 3788' Confining Zone
-3788' Garden Gulch Mem.*

-4300' - 29' 80% Bond

TUBING

SIZE/GRADE/WT: 2-7/8" / J-55 / 6.5#

NO. OF JOINTS: 182 jts (5691.17')

TUBING ANCHOR: 5703.17' KB

NO. OF JOINTS: 2 jts (62.75')

SEATING NIPPLE: 2-7/8" (1.10')

SN LANDED AT: 5768.72' KB

NO. OF JOINTS: 2 jts (62.41')

TOTAL STRING LENGTH: BOT @ 5832.68' W/12' KB

PERFORATION RECORD

| | | | |
|----------|-------------|--------|-----------|
| 02/07/05 | 5722'-5747' | 4 JSPP | 100 holes |
| 02/07/05 | 5680'-5697' | 4 JSPP | 68 holes |
| 02/07/05 | 5137'-5146' | 4 JSPP | 36 holes |
| 02/07/05 | 4759'-4779' | 4 JSPP | 80 holes |

Packer @ 4724'

4759'-4779'

-4780' Douglas Creek

5137'-5146'

5680'-5697'

5722'-5747'

PBTD @ 5955'

SHOE @ 5999'

TD @ 6010'

-5900' Base Carbonate

-6020' Est Westch

NEWFIELD

Federal 7-4-9-18

1984 FNL & 1979 FEL

SWNE Sec. 4, T9S R18E

Utah, County

API# 43-047-35474; Lease# UTL-17424

APPENDIX B

LOGGING AND TESTING REQUIREMENTS

Logs.

Logs will be conducted according to current UIC guidance. It is the responsibility of the permittee to obtain and use guidance prior to conducting any well logging required as a condition of this permit.

NO LOGGING REQUIREMENTS

Tests.

Tests will be conducted according to current UIC guidance. It is the responsibility of the permittee to obtain and use guidance prior to conducting any well test required as a condition of this permit.

| WELL NAME: Federal 7-4-9-18 | |
|------------------------------------|--------------------------------------------------------------------------------------------------------|
| TYPE OF TEST | DATE DUE |
| Radioactive Tracer Survey (2) | Within 180 days following commencement of injection and at least once every five (5) years thereafter. |
| Pore Pressure | Prior to authorization to inject. |
| Step Rate Test | Within 180 days following commencement of injection. |
| Standard Annulus Pressure | Prior to authorization to inject and at least once every five (5) years thereafter. |

APPENDIX C

OPERATING REQUIREMENTS

MAXIMUM ALLOWABLE INJECTION PRESSURE:

Maximum Allowable Injection Pressure (MAIP) as measured at the surface shall not exceed the pressure(s) listed below.

| WELL NAME | MAXIMUM ALLOWED INJECTION PRESSURE (psi) |
|------------------|------------------------------------------|
| | ZONE 1 (Upper) |
| Federal 7-4-9-18 | 1,355 |

INJECTION INTERVAL(S):

Injection is permitted only within the approved injection interval listed below. Injection perforations may be altered provided they remain within the approved injection interval and the Permittee provides notice to the Director in accordance with Part II, Section A, Paragraph 6. Specific injection perforations can be found in Appendix A.

| WELL NAME: Federal 7-4-9-18 | | | |
|-----------------------------|-----------------------------------------|--------|----------------------------------|
| FORMATION NAME | APPROVED INJECTION INTERVAL (KB, ft) | | FRACTURE GRADIENT (psi/ft) |
| | TOP | BOTTOM | |
| Green River | 3,788.00 - 6,020.00 | | 0.720 |

ANNULUS PRESSURE:

The annulus pressure shall be maintained at zero (0) psi as measured at the wellhead. If this pressure cannot be maintained, the Permittee shall follow the procedures listed under Part II, Section C. 6. of this permit.

MAXIMUM INJECTION VOLUME:

There is no limitation on the number of barrels per day (bbls/day) of water that shall be injected into this well, provided further that in no case shall injection pressure exceed that limit shown in Appendix C.

APPENDIX D

MONITORING AND REPORTING PARAMETERS

This is a listing of the parameters required to be observed, recorded, and reported. Refer to the permit Part II, Section D, for detailed requirements for observing, recording, and reporting these parameters.

| OBSERVE MONTHLY AND RECORD AT LEAST ONCE EVERY THIRTY DAYS | |
|------------------------------------------------------------|-------------------------------------------------------------|
| OBSERVE AND RECORD | Injection pressure (psig) |
| | Annulus pressure(s) (psig) |
| | Injection rate (bbl/day) |
| | Fluid volume injected since the well began injecting (bbls) |

| ANNUALLY | |
|----------|----------------------------------------------|
| ANALYZE | Injected fluid total dissolved solids (mg/l) |
| | Injected fluid specific gravity |
| | Injected fluid specific conductivity |
| | Injected fluid pH |

| ANNUALLY | |
|----------|--------------------------------------------------------------|
| REPORT | Each month's maximum and averaged injection pressures (psig) |
| | Each month's maximum and averaged annulus pressure(s) (psig) |
| | Each month's averaged injection rate (bbl/day) |
| | Fluid volume injected since the well began injecting (bbl) |
| | Written results of annual injected fluid analysis |
| | Sources of all fluids injected during the year |

Records of all monitoring activities must be retained and made available for inspection at the following location:

**Newfield Production Company
1401 Seventeenth Street - Suite 1000
Denver, CO 80202**

APPENDIX E

PLUGGING AND ABANDONMENT REQUIREMENTS

See diagram.

All cement plugs will be set with tubing.

9.2 ppg plugging gel, or fresh water weighted with bentonite or treated brine will be placed between all cement plugs.

The following Plugging and Abandonment Plan, as proposed by the permittee, is predicated on the permittee not revising the injection perforations cited on the schematic diagram of well during construction/conversion. Should the uppermost perforations (4759 feet to 4779 feet) be modified by shallower perforations in construction, the EPA will modify the P&A Plan accordingly.

PLUG NO. 1: A Cast Iron Bridge Plug (CIBP) at 4664 feet with 100 feet of Class "G" cement on CIBP.

PLUG NO. 2: Set a 250-foot cement plug (2000 feet to 2250 feet) across the top of the Green River Formation, which cement interval will cover a water zone..

PLUG NO. 3: Perforate 345 feet with 4 JSPF. Circulate Class "G" cement down the 5-1/2 inch casing and up the 5-1/2 inch X 8-5/8 inch casing annulus to the surface.

Federal 7-4-9-18

Spud Date: 1/10/05

Put on Production: 2/16/05

GL: 4937' KB: 4949'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts. (296.39') *B250 ASDW, <200'*

DEPTH LANDED: 306.39' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 160 sxs Class "G" cement, est 6 bbls cement to surf.

Initial Production: 38BOPD,
34MCFD, 17BWPDProposed P&A
Wellbore DiagramPRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#


LENGTH: 140 jts. (5996.71')

DEPTH LANDED: 5998.71' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 350 sxs Prem. Lite II mixed & 500 sxs 50/50 POZ.

CEMENT TOP AT: 350'

**NEWFIELD**

Federal 7-4-9-18
1984 FNL & 1979 FEL
SW/NE Sec. 4, T9S R18E
Uintah, County
API# 43-047-35474; Lease# UTU-17424

APPENDIX F

CORRECTIVE ACTION REQUIREMENTS

No corrective action is deemed necessary for this project.

STATEMENT OF BASIS

NEWFIELD PRODUCTION COMPANY

**FEDERAL 7-4-9-18
UINTAH COUNTY, UT**

EPA PERMIT NO. UT21039-07060

CONTACT: Emmett Schmitz
U. S. Environmental Protection Agency
Ground Water Program, 8P-W-GW
999 18th Street, Suite 300
Denver, Colorado 80202-2466
Telephone: 1-800-227-8917 ext. 6174

**RECEIVED
OCT 02 2006
DIV. OF OIL, GAS & MINING**

This STATEMENT OF BASIS gives the derivation of site-specific UIC Permit conditions and reasons for them. Referenced sections and conditions correspond to sections and conditions in the Permit.

UIC Permits specify the conditions and requirements for construction, operation, monitoring and reporting, and plugging of injection wells to prevent the movement of fluids into underground sources of drinking water (USDWs). Under 40 CFR 144 Subpart D, certain conditions apply to all UIC Permits and may be incorporated either expressly or by reference. General Permit conditions for which content is mandatory and not subject to site-specific differences (40 CFR Parts 144, 146 and 147) are not discussed in this document.

Upon the Effective Date when issued, the Permit authorizes the conversion and operation of a "new" injection well or wells governed by the conditions specified in the Permit. The Permit is issued for the operating life of the injection well or project unless terminated for reasonable cause under 40 CFR 144.39, 144.40 and 144.41. The Permit is subject to EPA review at least once every five (5) years to determine if action is required under 40 CFR 144.36(a).

PART I. General Information and Description of Facility

Newfield Production Company
1401 Seventeenth Street
Suite 1000
Denver, CO 80202

on

November 17, 2005

submitted an application for an Underground Injection Control (UIC) Program Permit or Permit Modification for the following injection well or wells:

Federal 7-4-9-18
1984' FNL & 1979' FEL, SWNE S4, T9S, R18E
Uintah County, UT

Regulations specific to Uintah-Ouray Indian Reservation injection wells are found at 40 CFR 147 Subpart TT.

The application, including the required information and data necessary to issue or modify a UIC Permit in accordance with 40 CFR Parts 144, 146 and 147, was reviewed and determined by EPA to be complete.

The Permit will expire upon delegation of primary enforcement responsibility (primacy) for applicable portions of the UIC Program to the Ute Indian Tribe or the State of Utah unless the delegated agency has the authority and chooses to adopt and enforce this Permit as a Tribal or State Permit.

TABLE 1.1 shows the status of the well or wells as "New", "Existing", or "Conversion" and for Existing shows the original date of injection operation. Well authorization "by rule" under 40 CFR Part 144 Subpart C expires automatically on the Effective Date of an issued UIC Permit.

The Federal No. 7-4-9-18 is currently an active Green River Formation oil well. The applicant intends to convert the subject facility to a Green River Formation enhanced recovery injection well.

| TABLE 1.1 | | |
|---------------------------------|-------------|-------------------|
| WELL STATUS / DATE OF OPERATION | | |
| CONVERSION WELLS | | |
| Well Name | Well Status | Date of Operation |
| Federal 7-4-9-18 | Conversion | N/A |

PART II. Permit Considerations (40 CFR 146.24)

The proposed injection well is located in the Newfield Production Company Greater Monument Butte area near the center of the broad, gently northward dipping south flank of the Uinta Basin. The beds dip at about 200'/mile, and there are no known surface folds or faults in the field. The lower 600' to 800' of the Uinta Formation, generally consisting of 5' to 20' thick brown lenticular fluvial sandstone and interbedded varicolored shales, outcrops at the surface in this area. The Uinta is underlain by the Green River Formation which consists of lake (lacustrine) margin sandstones, limestone and shale beds that were deposited along the edges and on the broad level floor of Lake Uinta as it expanded and contracted through time. Underlying the Green River Formation is the Wasatch Formation, which is approximately 2400' thick in this area and consists of red alluvial shales and siltstone with scattered lenticular sandstones usually 10' to 50' thick. Below the Wasatch Formation is the Mesaverde Formation; a series of interbedded continental deposits of shale, sandstone, and coal. Water samples from Mesaverde sands in the nearby Natural Buttes Unit yield highly saline water.

The Uinta Basin is a topographic and structural trough encompassing an area of more than 9300 square mi (14,900 km) in northeast Utah. The basin is sharply asymmetrical, with a steep north flank bounded by the east-west-trending Uinta Mountains, and a gently dipping south flank. The Uinta Basin formed in Paleocene to Eocene time, creating a large area of internal drainage which was filled by ancestral Lake Uinta. Deposition in and around Lake Uinta consisted of open- to marginal-lacustrine sediments that make up the Green River Formation. Alluvial red-bed deposits that are laterally equivalent to and intertongue with the Green River make up the Colton Formation (Wasatch). More than 450 million barrels of oil (63 MT) have been produced from the Green River and Wasatch Formations in the Uinta Basin. The southern shore of Lake Uinta was very broad and flat, which allowed large transgressive and regressive shifts in the shoreline in response to climatic and tectonic-induced rise and fall of the lake. The cyclic nature of Green River deposition in the southern shore area resulted in numerous stacked deltaic deposits. Distributary-mouth bars, distributary channels, and near-shore bars are the primary producing sandstone reservoirs in the area (Ref: "Reservoir Characterization of the Lower Green River Formation, Southwest Uinta Basin, Utah Biannual Technical Progress Report 4/1/99 - 9/30/99", by C. D. Morgan, Program Manager, November 1999, Contract DE-AC26-98BC15103). The Tertiary Duchesne River Formation alluvium generally is present at the surface in this area.

Throughout the current Newfield Production Company area of enhanced recovery injection activity, i.e., T8-9S - R15-19E, Green River Formation water analyses generally exhibit total dissolved (TDS) content well in excess of 10,000 mg/l. A few recent applications for well conversion to enhanced recovery injection contain Green River water analyses with TDS approximating 10,000 mg/l. The State of Utah-Natural Resources ascribes low TDS values to several possibilities involving dilution of Green River water with high TDS values, e.g., recharge of the Green River Formation via Green River Formation outcrop on the Book Cliffs/Roan Cliffs; injection of very low TDS Johnson Water District Reservoir source water; and percolation of surface water via deep-seated Gilsonite veins penetrating lower Green River Members.

Geologic Setting (TABLE 2.1)

TABLE 2.1
GEOLOGIC SETTING
Federal 7-4-9-18

| Formation Name | Top (ft) | Base (ft) | TDS (mg/l) | Lithology |
|----------------|----------|-----------|-------------|--------------------------------------------------------------------------------------------------------|
| Uinta | 0.00 | 2,172.00 | < 10,000.00 | Predominantly fluvial sand and shale deposits with some interbedded lacustrine carbonates. |
| Green River | 2,172.00 | 6,020.00 | 17,675.00 | Predominantly lacustrine carbonate-sand-shale deposition with interbedded fluvial sand-shale deposits. |

Proposed Injection Zone(s) (TABLE 2.2)

An injection zone is a geological formation, group of formations, or part of a formation that receives fluids through a well. The proposed injection zones are listed in TABLE 2.2.

Injection will occur into an injection zone that is separated from USDWs by a confining zone which is free of known open faults or fractures within the Area of Review.

The approved interval for enhanced recovery injection is the gross interval between the top of the Garden Gulch Member at 3788 feet and the top of the Wasatch Formation which is estimated to be 6020 feet.

TABLE 2.2
INJECTION ZONES
Federal 7-4-9-18

| Formation Name | Top (ft) | Base (ft) | TDS (mg/l) | Fracture Gradient (psi/ft) | Porosity | Exempted?* |
|----------------|----------|-----------|------------|----------------------------|----------|------------|
| Green River | 3,788.00 | 6,020.00 | 17,675.00 | 0.720 | | N/A |

* C - Currently Exempted
E - Previously Exempted
P - Proposed Exemption
N/A - Not Applicable

Confining Zone(s) (TABLE 2.3)

A confining zone is a geological formation, part of a formation, or a group of formations that limits fluid movement above the injection zone. The confining zone or zones are listed in TABLE 2.3.

The Confining Zone occurs at the top of the Garden Gulch Member from 3650 feet and 3788 feet.

TABLE 2.3
CONFINING ZONES
Federal 7-4-9-18

| Formation Name | Formation Lithology | Top (ft) | Base (ft) |
|----------------|---------------------|----------|-----------|
| Green River | Shale | 3,650.00 | 3,788.00 |

Underground Sources of Drinking Water (USDWs) (TABLE 2.4)

Aquifers or the portions thereof which contain less than 10,000 mg/l total dissolved solids (TDS) and are being or could in the future be used as a source of drinking water are considered to be USDWs. The USDWs in the area of this facility are identified in TABLE 2.4.

The State of Utah "Water Wells and Springs", <http://NRWRT1.STATE.UT.US>, identifies no public water supply wells within the one-quarter (1/4) mile Area-of-Review (AOR) around the Federal No. 7-4-9-18

Technical Publication No. 92: State of Utah, Department of Natural Resources, cites the base of Underground Sources of Drinking Water (USDW) in the Uinta Formation, approximately 200 feet from the surface.

TABLE 2.4
UNDERGROUND SOURCES OF DRINKING WATER (USDW)
Federal 7-4-9-18

| Formation Name | Formation Lithology | Top (ft) | Base (ft) | TDS (mg/l) |
|----------------|---------------------------------------|----------|-----------|-------------|
| Uinta | Predominantly fluvial sand and shale. | 0.00 | 200.00 | < 10,000.00 |

PART III. Well Construction (40 CFR 146.22)

The Federal No. 7-4-9-18 was drilled to a total depth of 6010 (KB) feet in the Basal Carbonate Member of the Green River Formation.

Surface casing (8-5/8 inch) was set at a depth of 306.39 feet (KB) in a 12-1/4 inch hole using 160 sacks of Class "G" cement which was circulated to the surface.

Production casing (5-1/2 inch) was set at a depth of 5998.71 feet (KB) in a 7-7/8 inch hole with 350 sacks of Premium Lite II and 500 sacks of 50/50 poz mix. This well construction is considered adequate to protect USDWs.

The EPA calculates the top of cement as 501 feet from the surface.

The schematic diagram shows the proposed current injection perforations in the Garden Gulch and Douglas Creek Members of the Green River Formation. Additional perforations may be added at a later time between the depths of 3788 feet and the top of the Wasatch Formation (Estimated to be 6020 feet) provided the operator first notifies the Director and later submits an updated well completion report (EPA Form 7520-12) and schematic diagram.

The packer will be required to be set no higher than 100 feet above the top perforation.

TABLE 3.1
WELL CONSTRUCTION REQUIREMENTS
Federal 7-4-9-18

| Casing Type | Hole Size (in) | Casing Size (in) | Cased Interval (ft) | Cemented Interval (ft) |
|-------------|----------------|------------------|---------------------|------------------------|
| Surface | 12.25 | 8.63 | 0.00 - 306.39 | 0.00 - 306.39 |
| Production | 7.88 | 5.50 | 0.00 - 5,998.71 | 501.00 - 5,998.71 |

The approved well completion plan will be incorporated into the Permit as APPENDIX A and will be binding on the Permittee. Modification of the approved plan is allowed under 40 CFR 144.52(a)(1) provided written approval is obtained from the Director prior to actual modification.

Casing and Cementing (TABLE 3.1)

The construction plan for the well or wells proposed for conversion to an injection well was evaluated and determined to be in conformance with standard practices and guidelines that ensure well injection does not result in the movement of fluids into USDWs. Well construction and conversion details for the well or wells are shown in TABLE 3.1.

Tubing and Packer

Injection tubing is required to be installed from a packer up to the surface inside the well casing. The packer will be set above the uppermost perforation. The tubing and packer are designed to prevent injection fluid from coming into contact with the outermost casing.

Tubing-Casing Annulus (TCA)

The TCA allows the casing, tubing and packer to be pressure-tested periodically for mechanical integrity, and will allow for detection of leaks. The TCA will be filled with fresh water treated with a corrosion inhibitor or other fluid approved by the Director.

The tubing/casing annulus must be kept closed at all times so that it can be monitored as required under the conditions of the Permit.

Monitoring Devices

The permittee will be required to install and maintain wellhead equipment that allows for monitoring pressures and providing access for sampling the injected fluid. Required equipment may include but is not limited to: 1) shut-off valves located at the wellhead on the injection tubing and on the TCA; 2) a flow meter that measures the cumulative volume of injected fluid; 3) fittings or pressure gauges attached to the injection tubing and the TCA for monitoring the injection and TCA pressure; and 4) a tap on the injection line, isolated by shut-off valves, for sampling the injected fluid.

All sampling and measurement taken for monitoring must be representative of the monitored activity.

PART IV. Area of Review, Corrective Action Plan (40 CFR 144.55)

**TABLE 4.1
AOR AND CORRECTIVE ACTION**

| Well Name | Type | Status (Abandoned Y/N) | Total Depth (ft) | TOC Depth (ft) | CAP Required (Y/N) |
|------------------|----------|---------------------------|---------------------|-------------------|-----------------------|
| Federal 2-4-9-18 | Producer | No | 5,960.00 | 1,424.00 | No |
| Federal 6-4-9-18 | Producer | No | 6,050.00 | 703.00 | No |
| Federal 8-4-9-18 | Producer | No | 6,050.00 | 865.00 | No |

TABLE 4.1 lists the wells in the Area of Review ("AOR") and shows the well type, operating status, depth, top of casing cement ("TOC") and whether a Corrective Action Plan ("CAP") is required for the well.

Area Of Review

Applicants for Class I, II (other than "existing" wells) or III injection well Permits are required to identify the location of all known wells within the injection well's Area of Review (AOR) which penetrate the injection zone, or in the case of Class II wells operating over the fracture pressure of the formation, all known wells within the area of review that penetrate formations which may be affected by increased pressure. Under 40 CFR 146.6 the AOR may be a fixed radius of not less than one quarter (1/4) mile or a calculated zone of endangering influence. For Area Permits, a fixed width of not less than one quarter (1/4) mile for the circumscribing area may be used.

Corrective Action Plan

For wells in the AOR which are improperly sealed, completed, or abandoned, the applicant shall

develop a Corrective Action Plan (CAP) consisting of the steps or modifications that are necessary to prevent movement of fluid into USDWs.

The CAP will be incorporated into the Permit as APPENDIX F and become binding on the permittee.

TABLE 4.1 lists the wells in the AOR, and shows the well type, operating status, depth, top of casing cement and whether a CAP is required for this well.

PART V. Well Operation Requirements (40 CFR 146.23)

TABLE 5.1
INJECTION ZONE PRESSURES
Federal 7-4-9-18

| Formation Name | Depth Used to Calculate MAIP (ft) | Fracture Gradient (psi/ft) | Initial MAIP (psi) |
|----------------|-----------------------------------|----------------------------|--------------------|
| Green River | 4,759.00 | 0.720 | 1,355 |

Approved Injection Fluid

The approved injection fluid is limited to Class II injection well fluids pursuant to 40 CFR § 144.6(b). For disposal wells injecting water brought to the surface in connection with natural gas storage operations, or conventional oil or natural gas production, the fluid may be commingled and the well used to inject other Class II wastes such as drilling fluids and spent well completion, treatment and stimulation fluid. Injection of non-exempt wastes, including unused fracturing fluids or acids, gas plant cooling tower cleaning wastes, service wastes and vacuum truck wastes, is prohibited.

The proposed injectate is a blend of source water from the Johnson Water District reservoir and produced water from adjacent wells. The TDS of the injectate is 9843 mg/l.

Injection Pressure Limitation

Injection pressure, measured at the wellhead, shall not exceed a maximum calculated to assure that the pressure used during injection does not initiate new fractures or propagate existing fractures in the confining zones adjacent to the USDWs.

The applicant submitted injection fluid density and injection zone data which was used to calculate a formation fracture pressure and to determine the maximum allowable injection pressure (MAIP), as measured at the surface, for this Permit,

TABLE 5.1 lists the fracture gradient for the injection zone and the approved MAIP, determined according to the following formula:

$$FP = [fg - (0.433 * sg)] * d$$

FP = formation fracture pressure (measured at surface)

fg = fracture gradient (from submitted data or tests)

d = depth to top of injection zone (or top perforation)

Cumulative injected fluid volume limits are set to assure that injected fluids remain within the boundary of the exempted area. Cumulative injected fluid volume is limited when injection occurs into an aquifer that has been exempted from protection as a USDW.

Mechanical Integrity (40 CFR 146.8)

1. there is no significant leak in the casing, tubing, or packer (Part I); and
2. there is no significant fluid movement into a USDW through vertical channels adjacent to the injection well bore (Part II).

The Permit requires that the well demonstrate mechanical integrity prior to injection and periodically thereafter. A demonstration of mechanical integrity includes both internal (Part I) and external (Part II). The methods and frequency for demonstrating Part I and Part II mechanical integrity are dependent upon well-specific conditions as explained below.

PART I MI: Internal MI will be demonstrated prior to beginning injection. Since this well is constructed with a standard casing, tubing, and packer configuration, a successful mechanical integrity test (MIT) is required to take place at least once every five (5) years. A demonstration of Part I MI is also required prior to resuming injection following any workover operation that affects the casing, tubing or packer. Part I MI may be demonstrated by a standard tubing-casing annulus pressure test using the maximum permitted injection pressure or 1000 psi, which ever is less, with a ten (10) percent or less pressure loss over thirty (30) minutes.

PART II MI: - The CBL indicates that cement does not meet minimum requirements needed to demonstrate zone isolation (at least 18 feet of continuous 80% bond, or better) through the confining zone. Therefore, further testing for Part II MI will be required prior to injection and at least once every five years thereafter. The demonstration shall be by temperature survey or other approved test. Approved tests for demonstrating Part II MI include a temperature survey, noise log or oxygen activation log, and Region 8 may also accept results of a radioactive tracer survey under certain circumstances.

PART VI. Monitoring, Recordkeeping and Reporting Requirements

At least once a year the permittee must analyze a sample of the injected fluid for total dissolved solids (TDS), specific conductivity, pH, and specific gravity. This analysis shall be reported to EPA

annually as part of the Annual Report to the Director. Any time a new source of injected fluid is added, a fluid analysis shall be made of the new source.

Instantaneous injection pressure, injection flow rate, cumulative fluid volume and TCA pressures must be observed on a weekly basis. A recording, at least once every thirty (30) days, must be made of the injection pressure, injection flow rate and cumulative fluid volume, and the maximum and average value for each must be determined for each month. This information is required to be reported annually as part of the Annual Report to the Director.

PART VII. Plugging and Abandonment Requirements (40 CFR 146.10)

All cement plugs will be set with tubing.

9.2 ppg plugging gel, or fresh water weighted with bentonite or treated brine will be placed between all cement plugs.

The following Plugging and Abandonment Plan, as proposed by the permittee, is predicated on the permittee not revising the injection perforations cited on the schematic diagram of well during construction/conversion. Should the uppermost perforations (4759 feet to 4779 feet) be modified by shallower perforations in construction, the EPA will modify the P&A Plan accordingly.

PLUG NO. 1: A Cast Iron Bridge Plug (CIBP) at 4664 feet with 100 feet of Class "G" cement on CIBP.

PLUG NO. 2: Set a 250-foot cement plug (2000 feet to 2250 feet) across the top of the Green River Formation, which cement interval will cover a water zone..

PLUG NO. 3: Perforate 345 feet with 4 JSPF. Circulate Class "G" cement down the 5-1/2 inch casing and up the 5-1/2 inch X 8-5/8 inch casing annulus to the surface.

Plugging and Abandonment Plan

Prior to abandonment, the well or wells must be plugged with cement in a manner which will not allow the movement of fluids either into or between USDWs. The plugging and abandonment plan is described in Appendix E of the Permit.

PART VIII. Financial Responsibility (40 CFR 144.52)

Demonstration of Financial Responsibility

The permittee is required to maintain financial responsibility and resources to close, plug, and abandon the underground injection operation in a manner prescribed by the Director. The permittee shall show evidence of such financial responsibility to the Director by the submission of a surety bond, or other adequate assurance such as financial statements or other materials acceptable to the Director. The Regional Administrator may, on a periodic basis, require the holder of a lifetime permit to submit a revised estimate of the resources needed to plug and abandon the well to reflect inflation of such costs, and a revised demonstration of financial responsibility if necessary. Initially, the operator has chosen to demonstrate financial responsibility with:

A Financial Statement was reviewed and approved by the EPA on July 19, 2006. The estimated Plug and Abandonment cost is \$33,000.

Financial Statement, received April 22, 2005

Evidence of continuing financial responsibility is required to be submitted to the Director annually.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:

USA UTU-17424

SUNDRY NOTICES AND REPORTS ON WELLS

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

SUNDANCE UNIT

8. WELL NAME and NUMBER:

FEDERAL 7-4-9-18

9. API NUMBER:

4304735474

10. FIELD AND POOL, OR WILDCAT:

MONUMENT BUTTE

1. TYPE OF WELL:

OIL WELL ☒

GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

NEWFIELD PRODUCTION COMPANY

3. ADDRESS OF OPERATOR:

Route 3 Box 3630

CITY Myton

STATE UT

ZIP 84052

PHONE NUMBER

435.646.3721

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: 1984 FNL 1979 FEL

COUNTY: UINTAH

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SWNE, 4, T9S, R18E

STATE: UT

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|----------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------|-----------------------------------------------------------|--------------------------------------------------------|--|
| <input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON | |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR | |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLAIR | |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 12/15/2006 | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL | |
| | <input checked="" type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/STOP) | <input type="checkbox"/> WATER SHUT-OFF | |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> OTHER: - | |
| | <input checked="" type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The subject well has been converted from a producing oil well to an injection well on 11/21/06. Two new interval was added, the A3 sds 5298'-5302', and the GB4 sds 4307'-4318' 4 JSPF, 60 shots. On 11/28/06 Dan Jackson with the EPA was contacted concerning the initial MIT on the above listed well. Permission was given at that time to perform the test on 12/01/06. On 12/01/06 the casing was pressured up to 1255 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 290 psig during the test. There was not an EPA representative available to witness the test. EPA# UT21039-07092 API# 43-047-35474

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) Bentri Park

TITLE Production Clerk

SIGNATURE

DATE 12/15/2006

(This space for State use only)

RECEIVED

DEC 21 2006

DIV. OF OIL, GAS & MINING

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 12/01/06
Test conducted by: Dale Giles
Others present: _____

| | | |
|------------------------------------------|----------------------------------------------------|----------------------------------------|
| Well Name: <u>Federal 7-4-9-18</u> | Type: ER SWD | Status: AC TA UC |
| Field: <u>Sundance unit</u> | | |
| Location: _____ | Sec: <u>4</u> T <u>9</u> N <u>10</u> R <u>18</u> W | County: <u>Uintah</u> State: <u>UT</u> |
| Operator: <u>Newfield Production Co.</u> | | |
| Last MIT: <u>1</u> / <u>1</u> | Maximum Allowable Pressure: _____ | PSIG |

Is this a regularly scheduled test? ☐ Yes ☐ No
Initial test for permit? ☒ Yes ☐ No
Test after well rework? ☐ Yes ☐ No
Well injecting during test? ☐ Yes ☐ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: 0 psig


| MIT DATA TABLE | Test #1 | Test #2 | Test #3 |
|------------------------|------------------------------------------------------------------------|-------------------------------------------------------------|-------------------------------------------------------------|
| TUBING | PRESSURE | | |
| Initial Pressure | <u>290</u> psig | psig | psig |
| End of test pressure | <u>290</u> psig | psig | psig |
| CASING / TUBING | ANNULUS | PRESSURE | |
| 0 minutes | <u>1255</u> psig | psig | psig |
| 5 minutes | <u>1255</u> psig | psig | psig |
| 10 minutes | <u>1255</u> psig | psig | psig |
| 15 minutes | <u>1255</u> psig | psig | psig |
| 20 minutes | <u>1255</u> psig | psig | psig |
| 25 minutes | <u>1255</u> psig | psig | psig |
| 30 minutes | <u>1255</u> psig | psig | psig |
| _____ minutes | psig | psig | psig |
| _____ minutes | psig | psig | psig |
| RESULT | <input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail | <input type="checkbox"/> Pass <input type="checkbox"/> Fail | <input type="checkbox"/> Pass <input type="checkbox"/> Fail |

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____



UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
USA UTU-17424
6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or
SUNDANCE UNIT

8. Well Name and No.
FEDERAL 7-4-9-18

9. API Well No.
4304735474

10. Field and Pool, or Exploratory Area
MONUMENT BUTTE

11. County or Parish, State
UINTAH, UT

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator
NEWFIELD PRODUCTION COMPANY

3a. Address Route 3 Box 3630
Myton, UT 84052

3b. Phone (include area code)
435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
1984 FNL 1979 FEL
SWNE Section 4 T9S R18E

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|-------------------------------------------------------|------------------------------------------------|-------------------------------------------|---------------------------------------------------|-------------------------------------------------|
| <input type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production(Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Subsequent Report | <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Final Abandonment | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other _____ |
| | <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug & Abandon | <input type="checkbox"/> Temporarily Abandon | Change Status, Put Well |
| | <input checked="" type="checkbox"/> Convert to | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | on Injection |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The above referenced well was put on injection at 2:00 p.m. on 2/20/07.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

RECEIVED
FEB 23 2007

DIV. OF OIL, GAS & MINING

LIC # UT21039-07060

I hereby certify that the foregoing is true and
correct (Printed/ Typed)

Mandie Crozier

Signature

Title

Regulatory Specialist

Date

02/22/2007

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or
certify that the applicant holds legal or equitable title to those rights in the subject lease
which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United
States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

1. Type of Well
☒ Oil Well ☐ Gas Well ☒ Other WSJ

2. Name of Operator
NEWFIELD PRODUCTION COMPANY

3a. Address Route 3 Box 3630
Myton, UT 84052

3b. Phone (include are code)
435 646 3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
1984 FNL 1979 FEL
SWNE Section 4 T9S R18E

5. Lease Serial No.
USA UTU-17424

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or
SUNDANCE UNIT

8. Well Name and No.
FEDERAL 7-4-9-18

9. API Well No.
4304735474

10. Field and Pool, or Exploratory Area
MONUMENT BUTTE

11. County or Parish, State
UINTAH, UT


12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|-------------------------------------------------------|----------------------------------------|-------------------------------------------|---------------------------------------------------|-------------------------------------------------|
| <input type="checkbox"/> Notice of Intent | <input type="checkbox"/> Acidize | <input type="checkbox"/> Deepen | <input type="checkbox"/> Production(Start/Resume) | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Subsequent Report | <input type="checkbox"/> Alter Casing | <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Reclamation | <input type="checkbox"/> Well Integrity |
| <input type="checkbox"/> Final Abandonment | <input type="checkbox"/> Casing Repair | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete | <input checked="" type="checkbox"/> Other _____ |
| | <input type="checkbox"/> Change Plans | <input type="checkbox"/> Plug & Abandon | <input type="checkbox"/> Temporarily Abandon | Step Rate Test _____ |
| | <input type="checkbox"/> Convert to | <input type="checkbox"/> Plug Back | <input type="checkbox"/> Water Disposal | _____ |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

A step rate test was conducted on the subject well on May 18, 2007. Results from the test indicate that the fracture gradient is .687 psi/ft. Therefore, Newfield is requesting that the maximum allowable injection pressure (MAIP) be changed to 1065 psi.


Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

| | |
|--------------------------------------------------------------------------------------------------|-------------------------------|
| I hereby certify that the foregoing is true and correct (Printed/ Typed) Cheyenne Bateman | Title Well Analyst Foreman |
| Signature  | Date 05/31/2007 |


| | | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|------------|
| Approved by _____ | Title _____ | Date _____ |
| Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. | Office _____ | |

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)



Federal 7-4-9-18
Sundance Unit
Step Rate Test
May 18, 2007



Start Pressure: 835 psi
Instantaneous Shut In Pressure (ISIP): 1095 psi
Top Perforation: 4307 feet
Fracture pressure (P_{fp}): 1065 psi
FG: 0.687 psi/ft

| Step | Rate(bpd) | Pressure(psi) |
|------|-----------|---------------|
| 1 | 200 | 860 |
| 2 | 400 | 905 |
| 3 | 600 | 950 |
| 4 | 800 | 995 |
| 5 | 1000 | 1040 |
| 6 | 1200 | 1075 |
| 7 | 1400 | 1105 |
| 8 | 1600 | 1130 |

| | | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|-------------------------------------------------------------|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-17424 |
| 1. TYPE OF WELL Water Injection Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052 | | 8. WELL NAME and NUMBER: FEDERAL 7-4-9-18 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1984 FNL 1979 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 04 Township: 09.0S Range: 18.0E Meridian: S | | 9. API NUMBER: 43047354740000 |
| 9. FIELD and POOL or WILDCAT: 8 MILE FLAT NORTH | | COUNTY: UINTAH |
| STATE: UTAH | | |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION | <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER | <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: 5 YR MIT |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 11/1/2011 | | | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | | | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | | | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 10/05/2011 Nathan Wiser with the EPA was contacted concerning the 5 year MIT on the above listed well. On 11/01/2011 the casing was pressured up to 1395 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 552 psig during the test. There was not an EPA representative available to witness the test. EPA ID: UT21039-07060

| | | |
|---------------------------------------------------|-------------------------------------|-------------------------------------------|
| NAME (PLEASE PRINT) Lucy Chavez-Naupoto | PHONE NUMBER 435 646-4874 | TITLE Water Services Technician |
| SIGNATURE N/A | DATE 11/3/2011 | |

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 11 / 1 / 11
Test conducted by: Lynna Monsen
Others present: _____

| | | |
|--------------------------------------------------------------------------------------------------------|-----------------------------------|------------------|
| Well Name: <u>Federal 7-4-9-18</u> | Type: ER SWD | Status: AC TA UC |
| Field: <u>Monument Butte</u> | | |
| Location: <u>SW/NE</u> Sec: <u>4</u> T <u>9</u> N <u>18</u> E/W County: <u>Uintah</u> State: <u>UT</u> | | |
| Operator: <u>New Field</u> | | |
| Last MIT: <u>1</u> / <u>1</u> | Maximum Allowable Pressure: _____ | PSIG |

Is this a regularly scheduled test? ☒ Yes ☐ No
Initial test for permit? ☐ Yes ☒ No
Test after well rework? ☐ Yes ☒ No
Well injecting during test? ☐ Yes ☒ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: 0 psig


| MIT DATA TABLE | Test #1 | Test #2 | Test #3 |
|------------------------|------------------------------------------------------------------------|-------------------------------------------------------------|-------------------------------------------------------------|
| TUBING | PRESSURE | | |
| Initial Pressure | <u>552</u> psig | psig | psig |
| End of test pressure | <u>552</u> psig | psig | psig |
| CASING / TUBING | ANNULUS PRESSURE | | |
| 0 minutes | <u>1395</u> psig | psig | psig |
| 5 minutes | <u>1395</u> psig | psig | psig |
| 10 minutes | <u>1395</u> psig | psig | psig |
| 15 minutes | <u>1395</u> psig | psig | psig |
| 20 minutes | <u>1395</u> psig | psig | psig |
| 25 minutes | <u>1395</u> psig | psig | psig |
| 30 minutes | <u>1395</u> psig | psig | psig |
| _____ minutes | psig | psig | psig |
| _____ minutes | psig | psig | psig |
| RESULT | <input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail | <input type="checkbox"/> Pass <input type="checkbox"/> Fail | <input type="checkbox"/> Pass <input type="checkbox"/> Fail |

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____



NEWFIELD

Schematic

Well Name: Federal 7-4-9-18

43-047-35474


| | | | | | | | |
|-------------------------------------|-------------------------------|---------------------------------|-------------------------------------|--------------------------------|------------------------------|----------------------------------------------|------------------|
| Surface Legal Location 04-9S-18E | | API/UWI 43047354740000 | Well RC 500151585 | Lease | State/Province Utah | Field Name GMBU CTB11 | County Uintah |
| Spud Date 1/10/2005 | Rig Release Date 1/19/2005 | On Production Date 2/16/2005 | Original KB Elevation (ft) 4,949 | Ground Elevation (ft) 4,937 | Total Depth All (TVD) (ftKB) | PBTD (All) (ftKB) Original Hole - 5,955.7 | |

Most Recent Job

| | | | | |
|-------------------------|------------------|---------------------------|-----------------------------|---------------------------|
| Job Category Testing | Primary Job Type | Secondary Job Type N/A | Job Start Date 11/1/2011 | Job End Date 11/1/2011 |
|-------------------------|------------------|---------------------------|-----------------------------|---------------------------|

TD: 6,010.0

Vertical - Original Hole, 9/15/2015 11:13:23 AM



NEWFIELD



Newfield Wellbore Diagram Data Federal 7-4-9-18

| | | | | | |
|-------------------------------------|------------------------|--------------------------------|--|----------------------------------------------|--|
| Surface Legal Location 04-9S-18E | | API/JWI 43047354740000 | | Lease | |
| County Uintah | State/Province Utah | Basin | | Field Name GMBU CTB11 | |
| Well Start Date 1/10/2005 | | Spud Date 1/10/2005 | | Final Rig Release Date 1/19/2005 | |
| Original KB Elevation (ft) 4,949 | | Ground Elevation (ft) 4,937 | | On Production Date 2/16/2005 | |
| Total Depth (ftKB) 6,010.0 | | Total Depth All (TVD) (ftKB) | | PBTD (All) (ftKB) Original Hole - 5,955.7 | |

Casing Strings

| Csg Des | Run Date | OD (in) | ID (in) | Wt/Len (lb/ft) | Grade | Set Depth (ftKB) |
|------------|-----------|---------|---------|----------------|-------|------------------|
| Surface | 1/10/2005 | 8 5/8 | 8.097 | 24.00 | J-55 | 306 |
| Production | 1/18/2005 | 5 1/2 | 4.950 | 15.50 | J-55 | 5,997 |

Cement

String: Surface, 306ftKB 1/12/2005

| | | | | |
|--------------------------------------------------------|--------------------------|------------------------------|--------------|------------------------------|
| Cementing Company BJ Services Company | Top Depth (ftKB) 12.0 | Bottom Depth (ftKB) 306.4 | Full Return? | Vol Cement Ret (bbl) |
| Fluid Description w/ 2% CaCL2 + 1/4#/sk Cello-Flake | Fluid Type Lead | Amount (sacks) 160 | Class G | Estimated Top (ftKB) 12.0 |

String: Production, 5,997ftKB 1/18/2005

| | | | | |
|-------------------------------------------------------------------------------------------------|---------------------------|--------------------------------|-----------------------|---------------------------------|
| Cementing Company BJ Services Company | Top Depth (ftKB) 350.0 | Bottom Depth (ftKB) 6,010.0 | Full Return? | Vol Cement Ret (bbl) |
| Fluid Description w/ 10% gel + 3 % KCL, 3#'s /sk CSE + 2# sk/kolseal + 1/4#'s/sk Cello Flake | Fluid Type Lead | Amount (sacks) 350 | Class Premilite II | Estimated Top (ftKB) 350.0 |
| Fluid Description W/ 2% Gel + 3% KCL, .5%EC1, 1/4# sk C.F. 2% gel. 3% SM | Fluid Type Tail | Amount (sacks) 500 | Class 50/50 Poz | Estimated Top (ftKB) 3,200.0 |

Tubing Strings

| | | | | | | | | |
|------------------------------|-----|---------|---------|------------|------------------------|----------|-----------------------------|------------|
| Tubing Description Tubing | | | | | Run Date 11/20/2006 | | Set Depth (ftKB) 4,270.5 | |
| Item Des | Jts | OD (in) | ID (in) | Wt (lb/ft) | Grade | Len (ft) | Top (ftKB) | Btm (ftKB) |
| Tubing | 136 | 2 7/8 | 2.441 | 6.50 | J-55 | 4,250.09 | 12.0 | 4,262.1 |
| Pump Seating Nipple | | 2 7/8 | 2.441 | | | 1.10 | 4,262.1 | 4,263.2 |
| Packer | | 5 1/2 | 2.441 | | | 7.35 | 4,263.2 | 4,270.5 |

Rod Strings

| | | | | | | | |
|-----------------|-----|---------|------------|----------|----------|------------------|------------|
| Rod Description | | | | Run Date | | Set Depth (ftKB) | |
| Item Des | Jts | OD (in) | Wt (lb/ft) | Grade | Len (ft) | Top (ftKB) | Btm (ftKB) |
| | | | | | | | |

Perforation Intervals

| Stage# | Zone | Top (ftKB) | Btm (ftKB) | Shot Dens (shots/ft) | Phasing (*) | Nom Hole Dia (in) | Date |
|--------|--------------------|------------|------------|----------------------|-------------|-------------------|------------|
| | GB4, Original Hole | 4,307 | 4,318 | 4 | | | 11/17/2006 |
| 3 | DS3, Original Hole | 4,759 | 4,779 | 4 | 90 | 0.430 | 2/10/2005 |
| 2 | B2, Original Hole | 5,137 | 5,146 | 4 | 90 | 0.430 | 2/10/2005 |
| | A3, Original Hole | 5,298 | 5,302 | 4 | | | 11/17/2006 |
| 1 | CP2, Original Hole | 5,680 | 5,697 | 4 | 90 | 0.410 | 2/7/2005 |
| 1 | CP3, Original Hole | 5,722 | 5,747 | 4 | 90 | 0.410 | 2/7/2005 |

Stimulations & Treatments

| Stage# | ISIP (psi) | Frac Gradient (psi/ft) | Max Rate (bbl/min) | Max PSI (psi) | Total Clean Vol (bbl) | Total Slurry Vol (bbl) | Vol Recov (bbl) |
|--------|------------|------------------------|--------------------|---------------|-----------------------|------------------------|-----------------|
| 1 | 1,610 | 0.72 | 25.2 | 1,597 | | | |
| 2 | 2,220 | 0.87 | 24.9 | 2,213 | | | |
| 3 | 2,000 | 0.85 | 25.2 | 2,154 | | | |

Proppant

| Stage# | Total Prop Vol Pumped (lb) | Total Add Amount |
|--------|----------------------------|------------------------|
| 1 | | Proppant Sand 90782 lb |
| 2 | | Proppant Sand 30242 lb |
| 3 | | Proppant Sand 66758 lb |

| | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-17424 |
| 1. TYPE OF WELL Water Injection Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY | | 7. UNIT or CA AGREEMENT NAME: GMBU (GRRV) |
| 3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052 | | 8. WELL NAME and NUMBER: FEDERAL 7-4-9-18 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1984 FNL 1979 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 04 Township: 09.0S Range: 18.0E Meridian: S | | 9. API NUMBER: 43047354740000 |
| PHONE NUMBER: 435 646-4825 Ext | | 9. FIELD and POOL or WILDCAT: 8 MILE FLAT NORTH |
| COUNTY: Uintah | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION | |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/5/2016 | <input checked="" type="checkbox"/> OTHER | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | OTHER: 5 YR MIT | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | OTHER: | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. 5 YR MIT performed on the above listed well. On 10/05/2016 the casing was pressured up to 1111 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbq pressure was 278 psig during the test. There was not an EPA representative available to witness the test. EPA #UT22197-07060 | | |
| Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 13, 2016 | | |
| NAME (PLEASE PRINT) Lucy Chavez-Naupoto | PHONE NUMBER 435 646-4874 | TITLE Water Services Technician |
| SIGNATURE N/A | DATE 10/6/2016 | |

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 10 / 5 / 2016
Test conducted by: Shannon Lezenby
Others present: _____

| | | |
|----------------------------------------------------------------------------------------------------------------|-----------------------------------------|------------------------------------------------------------|
| Well Name: <u>Federal 7-4-9-18</u> | Type: ER SWD | Status: AC TA UC -07060 |
| Field: <u>Greater Monument Butte</u> | | |
| Location: <u>7-4-9-18</u> Sec: <u>4</u> T <u>95</u> N/S R <u>18</u> E/W County: <u>Uintah</u> State: <u>ut</u> | | |
| Operator: <u>Shannon Lezenby</u> | | |
| Last MIT: <u> </u> / <u> </u> / <u> </u> | Maximum Allowable Pressure: <u>1372</u> | PSIG |

Is this a regularly scheduled test? ☒ Yes ☐ No
Initial test for permit? ☐ Yes ☒ No
Test after well rework? ☐ Yes ☒ No
Well injecting during test? ☐ Yes ☒ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: 01278 psig

| MIT DATA TABLE | | Test #1 | Test #2 | Test #3 |
|-----------------------------------------|------------------------------------------------------------------------|-------------------------------------------------------------|-------------------------------------------------------------|-------------------------------------------------------------|
| TUBING PRESSURE | | | | |
| Initial Pressure | <u>278</u> psig | | psig | psig |
| End of test pressure | <u>278</u> psig | | psig | psig |
| CASING / TUBING ANNULUS PRESSURE | | | | |
| 0 minutes | <u>1111.6</u> psig | | psig | psig |
| 5 minutes | <u>1111.4</u> psig | | psig | psig |
| 10 minutes | <u>1111.4</u> psig | | psig | psig |
| 15 minutes | <u>1110.8</u> psig | | psig | psig |
| 20 minutes | <u>1110.6</u> psig | | psig | psig |
| 25 minutes | <u>1110.6</u> psig | | psig | psig |
| 30 minutes | <u>1110.6</u> psig | | psig | psig |
| _____ minutes | psig | | psig | psig |
| _____ minutes | psig | | psig | psig |
| RESULT | <input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail | <input type="checkbox"/> Pass <input type="checkbox"/> Fail | <input type="checkbox"/> Pass <input type="checkbox"/> Fail | <input type="checkbox"/> Pass <input type="checkbox"/> Fail |

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____

7-4-9-18 5 yr MIT
10/5/2016 11:30:27 AM

